

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 32W H-13
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Section S T R

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 567 - 568.

Hilda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
H-13; South One-quarter Corner Section 34, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
H-13; South One-quarter Corner Section 34, T51N, R32W, on 5th Correction Line.

Reestablished corner midway on line between standard corners immediately to the east and west. Due to steeply angled subsurface rock, set witness corner easterly on section line a distance of 1.00 feet.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
H-13; South One-quarter Corner Section 34, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by Michael Mileski Date 28 December 1995
Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

H-13; South One-quarter Corner Section 34, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by an

Ironwood 6 N49°E 33 lks. (Gone)

and a

Birch 6 N43°W 13 lks. (Gone)

This corner was reestablished, but not remonumented, at proportionate distance between the southwest corner of Section 33, T51N, R32W and the southeast corner of Section 34, T51N, R32W by Michael Avery and Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 17 September 1982 to 30 September 1983 and approved 8 July 1985.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13; South One-quarter Corner Section 34, T51N, R32W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location for witness corner. This witness corner lies 1.00 feet easterly of the reestablished proportioned corner position.

Set 60d spike	S/side	9" Sugar Maple	N71°E	18.48'
Set 60d spike	W/side	8" Sugar Maple	S23°E	24.46'
Set 60d spike	W/side	12" Sugar Maple	S16°W	26.95'
Set 60d spike	S/side	11" Sugar Maple	N81°W	20.00'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".