

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga (County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 32W I-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R
4. Lot No. , Recorded Plat
5. Private Claims

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 607 - 608.

Handwritten signature: Theda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column J and row 13.

A. Description of original monument and accessories and/or subsequent restoration:

I-13; Section Corner common to Sections 34 and 35, T51N, R32W, on 5th Correction Line.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13; Section Corner common to Sections 34 and 35, T51N, R32W, on 5th Correction Line.

Found a 1 1/2" dia. iron pipe projecting 14" above ground in agreement with the local new bearing trees as recorded by the BLM and listed in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13; Section Corner common to Sections 34 and 35, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by Michael Mileski

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

I-13; Section Corner common to Sections 34 and 35, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 16 N54°E 51 lks.

(Recovered as ground level stump remains approximately 20" in dia.)

and a

Hemlock 6 N29°W 58 lks. (Gone)

This corner was recovered by Michael Avery and Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 17 September 1982 to 30 September 1983 and approved 8 July 1985. According to the field notes of this survey, a 1½" dia. iron pipe projecting 14" above ground was found in agreement with the remains of both U.S. bearing trees. The BLM did not remonument the corner nor record any new bearing trees. However the following local new bearing trees were noted by the BLM:

Sugar Maple 6 N35°E 30 lks.

(Set 60d spike NW/side N29°E 19.80')

Sugar Maple 6 S49°W 25 lks.

Basswood 18 N45°W 14 lks.

(Set 60d spike SW/side N49°W 9.24')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13; Section Corner common to Sections 34 and 35, T51N, R32W, on 5th Correction Line.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	N/side	11" Basswood	N75°E	13.23'
Set 60d spike	E/side	10" Red Maple	S05°E	18.52'
Set 60d spike	S/side	12" Sugar Maple	N84°W	20.20'
Set 60d spike	E/side	12" Basswood	N08°W	13.04'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".