

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga  
(County)

Located In:

Corner Code #

- 1. Public Land Survey      T 51N R 32W      J-13
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous              S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Section        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD THIS 28TH DAY  
OF DECEMBER A.D. 1995 AT 10:30 AM  
AND RECORDED IN LIBER 4 OF LAND  
CORNER RECORDATION ON PAGES  
565 - 566.

*Hella J. Robillard*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on December, 19 95  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-quarter Corner Section 35, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County  
12-19-95  
*[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13; South One-quarter Corner Section 35, T51N, R32W, on 5th Correction Line.

Found the BLM monument described in Part A to be consistent with its intended  
proportioned position and in agreement with the BLM new bearing trees.  
Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13; South One-quarter Corner Section 35, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by *[Signature]*

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

## A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-quarter Corner Section 35, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Black Ash 16 N47°E 54lks. (Gone)

and a

Black Ash 14 N37°W 24 lks. (Gone)

This corner was reestablished at proportionate distance between the southwest corner of Section 35, T51N, R32W and the south one-quarter corner of Section 31, T51N, R31W by Michael Avery and Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 17 September 1982 to 30 September 1983 and approved 8 July 1985. Mr. Avery and Mr. Douglas monumented the corner with a 5/8" x 36" aluminum pipe with 4" aluminum cap appropriately stamped as to location and noted the following new bearing trees:

Ash 8 N82°E 43½ lks.

and a

Yellow Birch 10 N76°W 68½ lks.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13; South One-quarter Corner Section 35, T51N, R32W, on 5th Correction Line.

Left existing monument in place adding "PA 345 1995" to the aluminum cap.

Set 60d spike	E/side	12" Black Ash	N22°E	26.43'
Set 60d spike	N/side	10" Black Ash	N80°E	19.57'
Set 60d spike	E/side	8" Black Ash	S27°E	8.40'
Set 60d spike	N/side	11" Black Ash	N80°W	19.04'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".