

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
609 - 610.

- 1. Public Land Survey T 51N R 32W K-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____

Helda J. Bohland

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13; Section Corner common to Sections 35 and 36, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13; Section Corner common to Sections 35 and 36, T51N, R32W, on 5th Correction Line.

Reestablished corner at proportionate distance along a latitudinal curve between the southwest corner of Section 35, T51N, R32W and the south one-quarter corner of Section 31, T51N, R31W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13; Section Corner common to Sections 35 and 36, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by [Signature]

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

K-13; Section Corner common to Sections 35 and 36, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 7 N43°E 19 lks. (Gone)

and a

Hemlock 6 N46°W 23 lks. (Gone)

This corner was considered to be lost during the course of a survey conducted by Michael Avery and Stephen Douglas of the Bureau of Land Management from 17 September 1982 to 30 September 1983 and approved 8 July 1985. The BLM did not remonument the corner.

The late Norman Thompson, RLS #4348 states in his field notes dated 2 December 1941 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that "there is a 2" iron pipe, 3 ft long, set in pile rocks for this corner".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13; Section Corner common to Sections 35 and 36, T51N, R32W, on 5th Correction Line.

Grouted a 1" dia. iron rod with 2" aluminum cap appropriately stamped as to location into a rock knob.

Set 60d spike	W/side	8" Red Maple	N19°E	150.36'
Set 60d spike	NW/side	8" Sugar Maple	N71°E	145.48'
Set 60d spike	N/side	8" Sugar Maple	N87°E	132.30'
Set 60d spike	NW/side	22" Red Maple	S63°W	89.07'
		2" iron pipe	N03°W	46.00'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".