

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>33</u> W. R. <u>33</u> E. W.	C13 & E13
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner C13: Standard Cor. on 5th Corr. Line between Sec. 31 & 32, T51N, R33W:
 Wood post (Not found. No subsequent monuments found.)
 Hemlock 18 N31E 18 (" " No subsequent accessories found.)
 Sugar 7 N50W 42 (" " No subsequent accessories found.)

Corner E13: Standard Cor. on 5th Corr. Line between Sec. 32 & 33, T51N, R33W:
 Wood post (Not found. No subsequent monuments found.)
 Maple 10 N47E 28 (" " No subsequent accessories found.)
 Birch 10 N42W 20 (" " No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner C13: Re-established 5/7/76 proportionately on line between Standard Corners 80.136 ch. E and 82.140 ch. W on 5th Correction Line.

Corner E13: Re-established 4/23/76 in approx. construction centerline of old E & W township road, midway between old fence lines on N & S sides of road and in line with old field edge to N. Found this position to agree with old field edge and fence for section line between Sec. 1 & 2, T50N, R34W, closing on the 5th Correction Line 7.843 ch. W of this point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner C13: 1" I. D. x 36" iron pipe with 3 3/4" aluminum cap.
 Red Maple 8 N45°E (mag.) 4.0 ft. "S32, NBT"
 Red Maple 4 N50°W (mag.) 11.5 ft. "S31, NBT"
 Sugar Maple 6 S30°E (mag.) 4.1 ft. "S 2, NBT"

Corner E13: 1" I.D. x 24" iron pipe with 3 3/4" aluminum cap.
 Red Maple 5 S21°W (mag.) 24.9 ft. " S 1, NBT"
 Elm 6 N48°E (mag.) 29.3 ft. "S33, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 19, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

