

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. <u>51</u> N. <u>X</u> , R. <u>33</u> W.	A13
2. PROPERTY CONTROLLING IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	, T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 10, 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Standard Corner on 5th Corr. Line bet. Sec. 31, T51N, R33W & Sec. 36, T51N, R34W:

Wood Post	(Not found. See "B" for subsequent monument.)
Birch 12 N35E 29	(" " No subsequent accessories found.)
Sugar 12 N40W 36	(" : " " " ")

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Rewitnessed a 1" bolt with 2" x 2" square head found in place while making a retracement survey in this area. Monument possibly set by a former local surveyor named Schwalm. Method used to set is not known, but the corner falls only 20.4 lks. S and 8.2 lks. E of its calculated proportionate position on the 5th Correction Line, which is well within the reasonable limits of probability as to original establishment.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" bolt (length unknown) with 2" x 2" square head, buried in road.
 Nail in Power Pole N24°W (mag.) 40.00 ft.
 Nail in 5" Apple tree S60°W 51.00 ft.

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 19, 1976

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

