

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Baraga Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 51N R 33W A-2* _____
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 715.

Relda Mc Intyre
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-2; West One-quarter Corner Section 6, T51N, R33W;
 Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a Birch 10 S70°W 9 lks. and a Hemlock 16 N33°W 23 lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-2; West One-quarter Corner Section 6, T51N, R33W;
 No evidence bearing upon the location of this corner was found. Reestablished the corner on line and at proportionate distance between the SW corner of section 6 and the NW corner of section 6. This position falls on the physical centerline of an unimproved, 10 foot wide, seasonal road which is located along the entire west line of section 6.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-2; West One-quarter Corner Section 6, T51N, R33W;
 Set a 1"(I.D.) x 18" galvanized iron pipe with a 2" aluminum cap stamped as to location 6 inches below the road surface.

Set 7" spike	E/side	12" Red Oak	N16°E	80.00'
Set 7" spike	N/side	11" Red Maple	N89°E	46.80'
Set 7" spike	NW/side	9" Yellow Birch	S41°W	48.35'
Set 7" spike	E/side	9" Yellow Birch	N29°W	59.30'
		Location Post	East	7.60'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

*This corner is also M-2 of T51N, R34W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County
[Signature]
12-18-96



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 18 Dec 1996
 LIBER 4 PAGE 715