

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | <u>A-3</u> |
| | T <u>51N</u> R <u>34W</u> | <u>M-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 623-624.

Thelma J. Philbrook
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

See back of form.

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

[Signature]
 7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

See back of form.

**SURVEY &
 REMONUMENTATION**

MAY 05 1997

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

See back of form.



Signed by *Michael Mileski* Date 12 July 1996
 Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 14 S70°W 8 lks. and a Birch 12 N60°W 29 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was found to be monumented " with an iron bolt, ½ in. diam., with a 1½ in. sq. head...at cor. of fences extending S. and W., from which a large hemlock stump hole, bears S70°W, 8 lks. dist., agreeing with the record position of an original hemlock bearing tree." The BLM did not remonument this corner nor did they note any accessories.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

Found a ½ inch diameter iron rod 20 inches in length with a 1½ inch square nut threaded onto one end. The other end is flattened with a hole in the center. From this monument a hemlock stump hole is located at record U.S. bearing and distance per BLM field notes. This monument is located in a north-south fence 7 feet south of a fence to the west and 18 feet west of the physical centerline of a ditched 10 foot wide north-south trail road known as Oliver Road. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position:

A-3; Section Corner common to Sections 6 and 7, T51N, R33W and Sections 1 and 12, T51N, R34W;

Replaced found monument with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 7" spike	SE/side	13" Sugar Maple	N48°E	45.93'
Set 7" spike	S/side	16" Sugar Maple	S66°E	59.98'
Set 7" spike	NW/side	14" Sugar Maple	S50°W	61.25'
Set 7" spike	SW/side	16" Sugar Maple	N34°W	17.55'
Set 7" spike	N/side	13" Sugar Maple	S80°W	27.21'
		Location Post	North	1.0'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION