

SURVEY & REMONUMENTATION

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>A-4 *</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 1ST DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 680-681.

Nelda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-4; West One-quarter Corner Section 7, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-4; West One-quarter Corner Section 7, T51N, R33W;

Accepted the BLM determination that this corner is lost. Found BLM copperweld 10 inches below the road surface and replaced with a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap. Corner location falls in the physical centerline of a 10 foot wide seasonal road which bears north. The physical centerline of a 20 foot wide, graded gravel road bears to the east and to the south. There are no significant fences within one-half of a mile either to the north or to the south. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-4; West One-quarter Corner Section 7, T51N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location 10 inches below the road surface.

- i) Set 7" spike NW/side Power Pole N37°E 41.06'
- ii) Set 7" spike W/side 10" Cedar S18°W 113.41'
- iii) Set 7" spike N/side 17" Balsam S88°W 64.02'
- iv) Location Post S89°W 17.3'

(i) and (iii) are BLM accessories and are further described in Part A.

(ii) is marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

* This corner is also M-4 of T51N, R34W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4	●	7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-09-96
NMA



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 31 Oct 1996

A. Description of original monument and accessories and/or subsequent restoration:

A-4; West One-quarter Corner Section 7, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 8 S57°W 29 lks.

and a

Hemlock 8 N37°W 28 lks.

This corner was considered lost and reestablished on line and at proportionate distance between the southwest corner of section 18, T51N, R33W and the northwest corner of section 7, T51N, R33W, both of which are probable U.S. corners, by the Bureau of Land Management during the course of a survey conducted by Stephen Douglas from 10 May 1984 to 10 November 1984 and approved 23 September 1985. The BLM monumented this position with a 9/16" x 30" copperweld and cap stamped as to location and noted the following accessories:

Power Pole N40°E 62½ lks. (41.25')
Set 7" spike directly below a small nail on the NW/side.
Measured N37°E 41.06'

and a

Spruce 15 N89°W 97 lks. (64.02')
Found a balsam presently alive and 17" in diameter having a mostly open lower blaze with scribing visible. I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.
Set 7" spike N/side Measured S88°W 64.02'

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION