

STATE OF MICHIGAN

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 33W A-5*
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

RECEIVED FOR RECORD THIS 1ST
DAY OF NOVEMBER, 1996 AT 10:30
A.M. AND RECORDED IN LIBER 4
OF LAND CORNER RECORDATION
RECORDS ON PAGES 682-683.

Nelda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-5; Section Corner common to Sections 7 and 18, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-5; Section Corner common to Sections 7 and 18, T51N, R33W;

Accepted the BLM determination that this corner is lost and reestablished corner on line and at proportionate distance between the southwest corner of section 18 and the northwest corner of section 7. Corner location falls 14 feet north of the physical centerline of a paved road to the west and approximately 2 feet east of the physical centerline of a road which is paved to the north and gravel to the south. From this position there is an old and down cedar post fence running to the east. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5; Section Corner common to Sections 7 and 18, T51N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location inside a monument box.

- Set 7" spike S/side 12" Cedar N78°E 39.11'
- Set 7" spike SW/side Power Pole S33°E 46.49'
- Set 7" spike SE/side 5" White Spruce S36°W 79.45'
- Set 7" spike SW/side 12" Cedar N50°W 113.95'

Owing to the somewhat residential nature of the area, the above new bearing trees were neither marked nor painted.

* This corner is also M-5 of T51N, R34W.



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 31 OCT 1996

A. Description of original monument and accessories and/or subsequent restoration:

A-5; Section Corner common to Sections 7 and 18, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 16 S47½°W 15 lks.

and a

Sugar 12 N22°W 17 lks.

This corner was considered lost and reestablished on line and at proportionate distance between the southwest corner of section 18, T51N, R33W and the northwest corner of section 7, T51N, R33W, both of which are probable U.S. corners, by the Bureau of Land Management during the course of a survey conducted by Stephen Douglas from 10 May 1984 to 10 November 1984 and approved 23 September 1985. The BLM did not monument this position.

The only significant east-west fence from the southwest corner of section 18 to the northwest corner of section 7 is located along the north one-sixteenth line of section 18. Immediately east of the one-sixteenth corner this fence lies within 3 feet of a split between the proportioned W¼ corner of section 18 and the proportioned NW corner of section 18.

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION