

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

_____	Located In:	Corner Code #
<u>Baraga</u>		
(County)		
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>A-6 *</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 1ST DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 684-685.

Nelda McIntyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-6; West One-quarter Corner Section 18, T51N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-6; West One-quarter Corner Section 18, T51N, R33W;

Accepted the BLM determination that this corner is lost. Found BLM copperweld disturbed by road grading. Reestablished corner on line and at proportionate distance from a control traverse between the southwest corner of section 18 and the northwest corner of section 7. Corner location is at the south end of a graded gravel road to the north and 7 feet east of the physical centerline of the same. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-6; West One-quarter Corner Section 18, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location 12" below the road surface.

- i) Set 7" spike NW/side 10" Sugar Maple N44°E 61.07'
- ii) Set 7" spike NE/side 12" Red Maple S34°E 57.80'
- iii) Set 7" spike SE/side 12" Sugar Maple S23°W 96.22'
- iv) Set 7" spike SW/side 14" Yellow Birch N41°W 63.54'
- Location Post S06°E 35.4'



(i) and (iv) are BLM new bearing trees and are further described in Part A.
(ii) and (iii) are marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

* This corner is also M-6 of T51N, R34W.

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 31 Oct 1996
LIBER 4 PAGE 684

A. Description of original monument and accessories and/or subsequent restoration:

A-6; West One-quarter Corner Section 18, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Lynn 8 S75°W 31 lks.

and a

Hemlock 9 N33°W 23 lks.

This corner was considered lost and reestablished on line and at proportionate distance between the southwest corner of section 18, T51N, R33W and the northwest corner of section 7, T51N, R33W, both of which are probable U.S. corners, by the Bureau of Land Management during the course of a survey conducted by Stephen Douglas from 10 May 1984 to 10 November 1984 and approved 23 September 1985. The BLM monumented this position with a 9/16" x 30" copperweld and cap stamped as to location and noted the following new bearing trees:

Maple 8 N49°E 93 lks. (61.38')
Found a sugar maple presently alive and 10" in diameter having a mostly
healed lower blaze with some scribing visible.
Set 7" spike NW/side Measured N44°E 61.07'

and a

Yellow Birch 10 N38°W 95 lks. (62.70')
Presently alive and 14" in diameter having a mostly open lower blaze
with scribing visible.
Set 7" spike SW/side Measured N41°W 63.54'

To each of the above BLM new bearing trees I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION