

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>A-7*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 1ST DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 686-687.

Richard McAntyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-7; Section Corner common to Sections 18 and 19, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-7; Section Corner common to Sections 18 and 19, T51N, R33W;

Found a 5/8" diameter aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location as set by the BLM in 1984 at the southeast side of an 8" diameter cedar kingpost having standing fences to the south and west and a down fence to the north. Wired to the southeast side of the kingpost is a very old, square 3" per side, cedar stake approximately 4 1/2 feet tall having scribing on square faces at the top too far gone to read. I did not find the identifiable remains of U.S. bearing trees from this monument. This monument was found to be in agreement with Mr. Crampton's new bearing trees as well as the BLM new bearing tree. Accepted as the best available evidence of the position of the original corner. I did not remonument the corner, but stamped "PA 345 1996" to the cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-7; Section Corner common to Sections 18 and 19, T51N, R33W;

Found a 5/8" diameter aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location.

Set 7" spike	SE/side	20" Hemlock	N48°E	13.08'
Set 7" spike	NE/side	8" Cedar	S67°E	7.18'
Set 7" spike	NW/side	9" Cedar	S59°W	56.43'
Set 7" spike	NE/side	18" Hemlock	N38°W	13.36'
		Location post	East	1.5'

Refer to Part A for further description of the above new bearing trees.

* This corner is also M-7 of T51N, R34W.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

109-96
[Signature]



Signed by *Michael Mileski*

Date 31 Oct 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

A-7; Section Corner common to Sections 18 and 19, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 16 S53°W 29 lks.

and a

Cedar 8 N45°W 14 lks.

According to a Land Corner Recordation Certificate filed by Robert Crampton, P.S. #24591 and recorded 30 August 1979 in Liber 1 page 350, an "old cedar post found, set a 1/2" iron bar at intersection of three old fences". Mr. Crampton noted the following new bearing trees:

14" Hemlock N45°E 13.08'

Presently alive and 20" in diameter. I added upper and lower face blazes and scribed the lower blaze "NBT". Set a 7" spike above a small nail and plastic tag marked "RLS 24591" on the SE/side.

Measured N48°E 13.08'

6" Cedar S85°E 7.18'

Presently alive and 8" in diameter. I added upper and lower face blazes and scribed the lower blaze "NBT". No nail and tag found in the tree. Set a 7" spike at the NE/side.

Measured N67°E 7.18'

12" Hemlock N45°W 13.36'

Presently alive and 18" in diameter. I added upper and lower face blazes and scribed the lower blaze "NBT". Set a 7" spike above a small nail and plastic tag marked "RLS 24591" on the NE/side.

Measured N38°W 13.36'

To all of the above Crampton new bearing trees, I painted the upper and lower blazes red as well as painted a red band around the tree at the upper blaze.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, Mr. Crampton's corner monument was replaced with a 5/8" x 36" aluminum post with cap appropriately stamped as to location. Mr. Douglas states in his field notes that the corner was

"perpetuated by persons unknown, and further perpetuated and recorded by Robert W. Crampton, R.L.S. No. 24591, in 1979, monumented with a cedar post, 3 ins. sq., firmly set, projecting 3 1/2 ft. above the ground, attached to a fence cor. with fences extending N., S. and W., mkd. 18 on NE., 19 on SE., and 13 on NW, weathered faces, alongside is an iron bar, 1/2 in. diam., firmly set, projecting 6 ins. above the ground, from which a large hemlock stump hole, bears S. 53°W., 29 lks. dist., agreeing with the record position of an original hemlock bearing tree."

The BLM noted the following bearing tree:

Cedar 7 S62°W 85 1/2 lks. (56.43')

Presently alive and 9" in diameter having an open lower face blaze with scribing visible. I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze. Set a 7" spike on the NW/side.

Measured S59°W 56.43'

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION