

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>A-9*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 13TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 704-705.

*Relda Mc Intyre*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-9; Section Corner common to Sections 19 and 30, T51N, R33W;  
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-9; Section Corner common to Sections 19 and 30, T51N, R33W;

Found a 1" x 25" iron pipe with a 1 1/2" brass cap stamped "LS 21583" in agreement with Mr. Taavola's accessories as described in Part A. This monument is located approximately 10 feet east of a down north-south fence. From this monument a 2 1/2" x 2 1/2" square wood post projecting 24 inches above the ground bears northwest a distance of 3 feet. I replaced Mr. Taavola's monument with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-9; Section Corner common to Sections 19 and 30, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location.

i) Set 7" spike	E/side	12" Sugar Maple	N21°E	10.02'
ii) Set 7" spike	SW/side	6" Sugar Maple	S60°E	6.04'
iii) Set 7" spike	N/side	6" Sugar Maple	S52°W	15.39'
iv) Set 7" spike	E/side	8" Twin Red Maple	N24°W	9.69'
		Location Post	North	1.0'

(i), (ii), and (iv) are Taavola new bearing trees and are further described in Part A.

(iii) is marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

\* This corner is also M-9 of T51N, R34W.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County  
10-30-96

*[Signature]*



Signed by *Michael Mileski*  
Surveyor's Michigan License No. 39091

Date 5 Nov 1996  
LIBER 4 PAGE 704

A. Description of original monument and accessories and/or subsequent restoration:

A-9; Section Corner common to Sections 19 and 30, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock        6        S49°W        40 lks.

and a

Hemlock        18        N27°W        37 lks.

According to Michigan Department of Transportation plans, file No. N-23-A-3, dated 1956, a 6" diameter cedar post was recovered and accepted as monumenting the corner position. The cedar post was replaced with an "iron pin" of unspecified size. The 1956 plans note the following new bearing trees:

4" Maple	N25°W	9.70'
6" Maple	N12°E	9.89'
3" Maple	S70°E	6.08'

According to a Land Corner Recordation Certificate filed by Brian Taavola, P.S. #21583 and recorded 19 February 1982 in Liber 4 page 21, a "1(in.) Iron Pin as per Michigan Department of Transportation Plans, File #N-23-A-3, Dated 1956" was recovered and that the "Plan wits checked o.k.". Mr. Taavola replaced the found 1" iron pin with " a ½(in.) rod & 1½" Brass cap stamped L.S. 21583 which is brazed to a 1" Iron pipe" and noted the following new bearing trees:

6" Maple                    S60°E                    6.04'

Found a sugar maple presently alive and 6" in diameter. I added upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike directly below a small double-headed nail and tag stamped "MDOT REF PT" on the SW/side.

Measured                    S60°E                    6.04'

12" Maple                    N20°E                    10.02'

Found a sugar maple presently alive and 12" in diameter. I added upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike directly below an overgrown double-headed nail and tag stamped "MDOT REF PT" on the E/side.

Measured                    N21°E                    10.02'

8" Twin Maple                N25°W                    9.69'

Found a red maple presently alive and 8" in diameter. I added upper and lower blazes and scribed the lower blaze "NBT". Set a 7" spike directly below a small double-headed nail and tag stamped "MDOT REF PT" on the E/side.

Measured                    N24°W                    9.69'

4" Yellow Birch                S50°W                    5.64'

Found standing dead.

To all of the above Taavola new bearing trees except the yellow birch, I painted the upper and lower blazes red as well as painted a red band around the tree at the upper blaze.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, Mr. Taavola's monument was recovered and accepted. The BLM field notes state that alongside Mr. Taavola's monument is

"a wooden post, 3 ins. sq., firmly set, projecting 2 ft. above ground, with no mks. visible, from which the remains of the orig. bearing trees:  
A hemlock stump hole, bears S.49°W., 40 lks. dist.  
A hemlock stump hole, bears N.27°W., 37 lks. dist."

The BLM did not remonument the corner nor note any new accessories.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION