

A. Description of original monument and accessories and/or subsequent restoration:

A-11; Section Corner common to Sections 30 and 31, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Birch 28 S78°W 18 lks.

and a

Sugar 8 N48°W 56 lks.

Per Michigan Department of Transportation plans, file No. N-23-A-3, dated 1956, this corner is indicated as being monumented with a 3/4" iron pin. The plans list the following accessories:

T. Pole S10°E 26.00'
P. Pole S55°E 74.68'
P. Pole N40°E 43.30'

This corner was further perpetuated by Brian Taavola, P.S. #21583 during a field survey conducted 20 November 1981. A Land Corner Recordation Certificate filed by Mr. Taavola and recorded 19 February 1982 in Liber 4 page 20 states "Found: 3/4" Iron pin 8" below surface, 26' West of C/L of Baraga Plains Road as per Michigan Department of Transportation Plans, File #N-23-A-3 using remaining witnesses". Mr. Taavola "replaced 3/4" Iron pin with 1/2" rod & 1 1/2" Brass cap stamped L.L.S. 21583 inside of a monument box" and noted the following accessories:

14" Spruce S42°W 50.32'

Presently alive and 19" in diameter. I added upper and lower blazes. The lower blaze was scribed "NBT". Both blazes as well as a red band around the tree at the upper blaze were painted red. No MDOT nail and tag was found.

Set a 7" spike on the W/side.

Measured S35°W 50.32'

32" Spruce S64°W 49.65'

Found standing dead with top broken off.

P. Pole S46°E 71.01'

Gone.

USC&GS BM#S149 S38°W 32.97'

Found in good condition with witness post.

Measured S32°W 32.10'

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION