

AUG 05 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 51N R 33W	A-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. A RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 490.

*Dennis R. Destrampe*  
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Dennis R. Destrampe in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post	No evidence of original corner found. 1 inch bolt found
Birch 12 N35E 29	April 10, 1973 and recorded November 17, 1976 in Liber 1,
Sugar 12 N40W 36	Page 269, by Arthur O. Enger, R.L.S. 13581

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found corner as described in Liber 1, Page 269, Land Corner Recordation.

1" bolt with 2"x2" square head, buried in road.  
 Corner accepted as found.

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Baraga County

12-1-93  
SKL



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 1" bolt with 1"x36" pipe with a 2½" brass cap 2½" below surface of gravel road. Baraga County Remonumentation brass cap stamped:

Witnesses:

- 7" Red Pine N32W 2.00' (Nail & tag "UPEA 18983" set)
- 6" Red Pine N70E 2.78' (Nail & tag "UPEA 18983" set)
- 10" Red Pine S26W 4.98' (Nail & tag "UPEA 18983" set)
- 11" Red Pine N76W 11.50' (Nail & tag "UPEA 18983" set)

S.G.

T51N

R34W | R33W  
 S36 | S31

S3

T50N R34W  
 1993

Signed by Dennis R. Destrampe

Date 4/20/94

Surveyor's Michigan License No. 18983