

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION
Baraga
(County)

Located In:

Corner Code #

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|-------|
| 1. Public Land Survey | T | <u>51N</u> | R | <u>33W</u> | <u>B-3</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 625-626.

Robert J. Schillard
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

B-3; One-quarter Corner common to Sections 6 and 7, T51N, R33W;

See back of form.

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County
[Signature]
7-10-96

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3	7	8	9	10	11	12						
4												
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-3; One-quarter Corner common to Sections 6 and 7, T51N, R33W;

Found BLM monument and all accessories as described in Part A. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-3; One-quarter Corner common to Sections 6 and 7, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 13 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

B-3; One-quarter Corner common to Sections 6 and 7, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a black ash post witnessed by a

Fir 8 S48°W 31 lks. and a Sugar 12 N27°E 15 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, a 2 inch diameter iron pipe projecting 2 feet above ground was found. The BLM field notes state that there is no remaining evidence of the original corner. Citing recognition by local surveyors and adjacent landowners as well as a harmonious relation with adjacent section corners the BLM accepted this monument and replaced it with a 2½" x 30" aluminum pipe with cap stamped as to location. The BLM noted the following new bearing trees:

Cedar 8 S35°W 126 lks. (83.16')
Found windthrown to the southeast.

Yellow Birch 15 N70°W 126 lks. (83.16')
Presently alive and 18" in dia. having a mostly open lower blaze with scribing visible.
Set 7" spike S/side Measured N75°W 82.16'

C. Description of monument for corner and accessories established to perpetuate locating the position:

B-3; One-quarter Corner common to Sections 6 and 7, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	NW/side	9" Sugar Maple	N18°E	27.28'
Set 7" spike	W/side	8" Red Maple	S01°W	26.84'
Set 7" spike	NW/side	9" Red Maple	S48°W	20.08'
		Location Post	North	0.7'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing tree was established by the BLM in 1984. Its condition is described in Part A. It was painted red.

Set 7" spike S/side 18" Yellow Birch N75°W 82.16'

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION