

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>B-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 23RD DAY OF OCTOBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 678-679.

*Thelma McAntypa*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County  
10-09-96  
*[Signature]*

A. Description of original monument and accessories and/or subsequent restoration:

B-5; One-quarter Corner common to Sections 7 and 18, T51N, R33W;  
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-5; One-quarter Corner common to Sections 7 and 18, T51N, R33W;

Found the BLM aluminum pipe and cap at the north side of an alive 11" diameter yellow birch and in agreement with both BLM new bearing trees. From this monument a severely decayed hemlock stump approximately 18" in diameter having roots intact is located at record U.S. bearing and distance. Also from this monument a dim stump hole is located at record U.S. bearing and distance. I did not remonument the corner but stamped the cap "PA 345 1996". Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-5; One-quarter Corner common to Sections 7 and 18, T51N, R33W;

Found a 5/8" diameter aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location.

- |                   |         |                  |       |        |
|-------------------|---------|------------------|-------|--------|
| i) Set 7" spike   | S/side  | 10" Sugar Maple  | N48°E | 7.51'  |
| ii) Set 7" spike  | NE/side | 13" Sugar Maple  | S76°E | 21.61' |
| iii) Set 7" spike | E/side  | 14" Yellow Birch | S26°E | 26.07' |
| iv) Set 7" spike  | N/side  | 13" Yellow Birch | S62°W | 25.82' |
| v) Set 7" spike   | NE/side | 13" Yellow Birch | N53°W | 53.82' |
|                   |         | Location Post    | North | 1.5'   |



(iii) is a BLM new bearing tree and is further described in Part A.

(i), (ii), (iv), and (v) are marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

Signed by *[Signature]*  
Surveyor's Michigan License No. 39091

Date 22 Oct 1996  
LIBER 4 PAGE 678

A. Description of original monument and accessories and/or subsequent restoration:

B-5; One-quarter Corner common to Sections 7 and 18, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a maple post witnessed by a

Hemlock        8        S47°W        17 lks.

and a

Hemlock        8        N17½°E       39 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented with a 5/8" x 36" aluminum pipe and cap from the remains of the original bearing trees. Specifically, the BLM field notes state:

" A decayed hemlock stump, 18 ins. diam., bears N.17½°E., 39 lks. dist., with no mks. visible."

and

" A hemlock stump hole, bears S.47°W., 17 lks. dist."

Furthermore the BLM stated that "the cor. point falls in a post hole with decayed wood fragments". The BLM noted the following new bearing trees:

Yellow Birch        12        North        55 lks. (36.30')  
Found standing dead and 15" in diameter having an open lower blaze with scribing visible. I did not mark nor paint this tree.  
Measured            N02°W        36.5' to CL

and a

Yellow Birch        10        S22°E        39½ lks. (26.07')  
Presently alive and 14" in diameter having a mostly open lower blaze with scribing visible. I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.  
Set 7" spike        E/side        Measured    S26°E        26.07'

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

COMMISSION