

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Baraga
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | B-9 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 13TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 700-701.

Helda McAnty
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6	5	4	3	2	1						
3													
4		7	8	9	10	11	12						
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9		●											
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
10-30-96

A. Description of original monument and accessories and/or subsequent restoration:

B-9; One-quarter Corner common to Sections 19 and 30, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9; One-quarter Corner common to Sections 19 and 30, T51N, R33W;

Found a 5/8" diameter aluminum pipe with 3 1/2" aluminum cap as set by the BLM in 1984. From this monument a severely decayed yellow birch stump approximately 28" in diameter is located at U.S. record bearing and distance. Also from this monument a severely decayed cedar stump approximately 20" in diameter is located at record U.S. bearing and distance. It appears that the scribed blaze on the fallen trunk of the cedar as described by the BLM has been cut out. I did not remonument the corner but stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9; One-quarter Corner common to Sections 19 and 30, T51N, R33W;

Found a 5/8" diameter aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location.

- | | | | | |
|-------------------|---------|---------------|-------|--------|
| i) Set 7" spike | SW/side | 10" Hemlock | N10°E | 18.91' |
| ii) Set 7" spike | E/side | 10" Cedar | N29°E | 69.30' |
| iii) Set 7" spike | E/side | 23" Hemlock | S17°E | 18.48' |
| iv) Set 7" spike | N/side | 9" Cedar | S60°W | 40.03' |
| | | Location Post | North | 1.0' |



(i) and (iv) are marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(ii) and (iii) are BLM new bearing trees and are further described in Part A.

Signed by *Michael Mileski*

Date 5 Nov 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

B-9; One-quarter Corner common to Sections 19 and 30, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Yellow Birch 12 S30°E 30 lks.

and a

Cedar 14 N23°W 35 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was found to be:

"monumented with the sharpened tip of a wooden post, 2 ins. sq., firmly set, 8 ins. below the surface; from which the remains of the orig. bearing trees:

A decayed yellow birch stump, 28 ins. diam., bears S.30°E., 30 lks. dist.; the fallen decayed trunk alongside has no mks. visible.

A cedar stump, 20 ins. diam., bears S.30°E., 30 lks. dist.; the fallen trunk alongside is mkd. ¼ on a partially chopped out blaze."

The BLM remonumented the corner with a 5/8" x 48" aluminum pipe and cap and noted the following new bearing trees:

Cedar 8 N28°E 105 lks. (69.30')
Presently alive and 10" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the E/side.
Measured N29°E 69.30'

Hemlock 22 S15°E 28 lks. (18.48')
Presently alive and 23" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the E/side.
Measured S17°E 18.48'

To each of the above BLM new bearing trees I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION