

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Spruce 20 S08°E 05 lks.

and a

Yellow Birch 9 S32°W 11 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was found to be monumented with a 2 inch diameter iron pipe "from which the remains of the orig. bearing trees: A stump hole, bears N. 2°E., 22 lks. dist. (and) A stump hole, bears N. 35°W., 11 lks. dist.". Also during this survey the BLM recovered and accepted similar monuments at the N 1/16 corner common to sections 5 and 6, the one-quarter corner common to sections 5 and 6, and the standard corner common to sections 31 and 32. At the latter two corners the BLM field notes state that the remains of the original bearing trees were recovered. The BLM did not remonument the corner nor did they note any accessories.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION