

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in _____

Baraga Located In: _____
 (County) _____

Corner Code # _____

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|-------|
| 1. Public Land Survey | T | <u>51N</u> | R | <u>33W</u> | <u>C-4</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 631 - 632.

Hilda J. Robillard
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on July, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-4; One-quarter Corner common to Sections 7 and 8, T51N, R33W;

See back of form.

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

[Signature]
 7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-4; One-quarter Corner common to Sections 7 and 8, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. From this monument a 10" dia. cedar post projecting 3 feet above ground having a 15" vertical cut scribed as to location bears east a distance of 0.6 feet. This monument is located 24 feet south of the physical centerline of an east-west 16' wide gravel road known as Cadeau Road. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4; One-quarter Corner common to Sections 7 and 8, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 13 July 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

C-4; One-quarter Corner common to Sections 7 and 8, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a hemlock post witnessed by a

Cedar 14 N60°E 03 lks. and a Fir 8 N63°W 30 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, a 6 inch diameter cedar post projecting 5 feet above ground with the north face scribed as to location was found and accepted. The BLM field notes state that no subsequent record of this corner was found. However, the cedar post is identical to other monuments established by Marshall J. Hall, Junior Engineer, U.S. Indian Service during his "Carp River Truck Trail" survey. The BLM remonumented the corner with a 2½" x 30" aluminum pipe with cap stamped as to location and noted the following new bearing trees:

Yellow Birch 7 S38°E 64 lks. (42.24')

Presently alive and 12" in dia. having a partially healed lower blaze with some scribing visible.

Set 7" spike SW/side Measured S43°E 42.24'

Yellow Birch 8 S50°W 64 lks. (42.24')

Presently alive and 16" in dia. having a healed lower blaze.

Set 7" spike SE/side Measured S47°W 42.24'

C. Description of monument for corner and accessories established to perpetuate locating the position:

C-4; One-quarter Corner common to Section 7 and 8, T51N, R33W;

Found a 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	W/side	24" Hemlock	N06°E	103.68'
Set 7" spike	W/side	12" Red Maple	S01°E	31.90'
		Location Post	North	1.0'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	SW/side	12" Yellow Birch	S43°E	42.24'
Set 7" spike	SE/side	16" Yellow Birch	S47°W	42.24'

The above BLM new bearing trees were painted red.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION