

**SURVEY &  
MONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in COMMISSION  
Baraga  
(County)

Located in:

Corner Code #

- 1. Public Land Survey                    T 51N R 33W                    C-5  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_  
     T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    in Section                                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous                        S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
    Property in Section                S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD THIS 30TH DAY  
OF JULY 1996 AT 10:30 A.M. AND  
RECORDED IN LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGES  
633 - 634.

*Heidi J. Rohlfend*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on July, 19 96

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, rec \_\_\_\_\_ d, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		●										
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

C-5; Section Corner common to Sections 7, 8, 17, and 18, T51N, R33W;

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*[Signature]*  
7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-5; Section Corner common to Sections 7, 8, 17, and 18, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. I could not conclusively verify the condition of the U.S. bearing trees. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-5; Section Corner common to Sections 7, 8, 17, and 18, T51N, R33W;

See back of form.



Signed by *[Signature]*

Date 13 July 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

C-5; Section Corner common to Sections 7, 8, 17, and 18, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch witnessed by a

Yellow Birch 18 S55°E 13 lks. and a Sugar 20 N38°W 45 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented with a 2½" x 30" aluminum pipe with cap stamped as to location from the remains of both U.S. bearing trees. Specifically, the BLM field notes state that from the monument " a stump hole, bears S55°E, 13 lks. dist. " and " a sugar maple stump, size indeterminate, bears N38°W, 45 lks. dist., with no mks. visible". The BLM noted the following new bearing trees:

Yellow Birch 15 N79°E 38 lks. (25.08')  
Presently alive and 17" in dia. having an open lower blaze with scribing visible.  
Set 7" spike S/side Measured N74°E 25.08'

Sugar Maple 10 S08°E 49 lks. (32.34')  
Presently alive and 15" in dia. having a mostly open lower blaze with scribing visible.  
Set 7" spike W/side Measured S08°E 32.34'

Sugar Maple 10 S37°W 46 lks. (30.36')  
Presently alive and 13" in dia. having a mostly open lower blaze with scribing visible.  
Set 7" spike SE/side Measured S32°W 30.36'

Sugar Maple 13 N42°W 70 lks. (46.20')  
Presently alive and 20" in dia. having an open lower blaze with scribing visible.  
Set 7" spike SW/side Measured N45°W 46.20'

C. Description of monument for corner and accessories established to perpetuate locating the position:

C-5; Section Corner common to Sections 7, 8, 17, and 18, T51N, R33W;

Found a 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	S/side	17" Yellow Birch	N74°E	25.08'
Set 7" spike	W/side	15" Sugar Maple	S08°E	32.34'
Set 7" spike	SE/side	13" Sugar Maple	S32°W	30.36'
Set 7" spike	SW/side	20" Sugar Maple	N45°W	46.20'

The above BLM new bearing trees were painted red.

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

COMMISSION