

SURVEY & REMONUMENTATION

FEB 23 1998

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in SECTION

Baraga	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	C-6	
	T _____ R _____	_____	
	T _____ R _____	_____	
	T _____ R _____	_____	
2. Property Controlling in Section	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	
	S _____ T _____ R _____	_____	

RECEIVED FOR RECORD THIS 31ST DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 809-810.

Nelda Bishop
REGISTER OF DEEDS FOR BARAGA COUNTY
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 30 July, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-6; One-quarter Corner common to Sections 17 and 18, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6; One-quarter Corner common to Sections 17 and 18, T51N, R33W;

Found a 2½" diameter aluminum pipe and cap as set by the BLM in 1984. The position of this monument was verified by a traverse. I did not remonument the corner, but stamped "PA 345 1997" to the cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6; One-quarter Corner common to Sections 17 and 18, T51N, R33W;

Found a 2½" diameter aluminum pipe with cap stamped as to location projecting 12" above ground.

Set 7" spike	SW/side	8" Sugar Maple	S18°E	22.52'
Set 7" spike	NE/side	20" Hemlock	N40°W	60.12'
Set 7" spike	W/side	10" Yellow Birch	N03°W	25.92'
		6' Steel fence post w/ yellow sign	North	3'

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
10-91-97
MT

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

See Part A for Bureau of Land Management new bearing trees.



LIBER 4 PAGE 809

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 23 Dec 1997

A. Description of original monument and accessories and/or subsequent restoration:

C-6; One-quarter Corner Common to Sections 17 and 18, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a hemlock post witnessed by a

Fir 10 S34°E 20 lks.

and a

Fir 12 N37°W 52 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between government corners immediately to the north and south. The BLM monumented the corner with a 2½" x 30" aluminum pipe and cap witnessed by a:

Hemlock 18 S70°E 73 lks. (48.18')
Presently alive and 18" in diameter having a partially healed lower blaze with scribing visible.

Set 7" spike SW/side Measured S70°E 47.95'

Hemlock 21 N85°W 78 lks. (51.48')
Presently alive and 22" in diameter having a healed lower blaze.

Set 7" spike N/side Measured N85°W 51.48'

To each of the above BLM new bearing trees, I added an upper blaze. Both blazes and a band around the tree at the upper blaze were painted red.

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION