

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
COMMISSION
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

_____ Baraga _____
(County)

Located In:

Corner Code #

- | | | | | | | |
|--------------------------------------|---|------------|---|------------|------------|-------|
| 1. Public Land Survey | T | <u>51N</u> | R | <u>33W</u> | <u>C-9</u> | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| | T | _____ | R | _____ | _____ | |
| 2. Property Controlling in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |
| 3. Miscellaneous Property in Section | S | _____ | T | _____ | R | _____ |
| | S | _____ | T | _____ | R | _____ |

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 639 - 640.

Robert J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on July, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-9; Section Corner common to Sections 19, 20, 29, and 30, T51N, R33W;

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
[Signature]
7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9; Section Corner common to Sections 19, 20, 29, and 30, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. From this monument I found a hemlock stump at S20°E a distance of 65 lks. and a stump hole at N20°W a distance of 5 lks. as stated by the BLM. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-9; Section Corner common to Sections 19, 20, 29, and 30, T51N, R33W;

See back of form.



Signed by [Signature] Date _____

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

C-9; Section Corner common to Sections 19, 20, 29, and 30, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch post witnessed by a

Hemlock 24 S20°E 61 lks. and a Hemlock 28 N20°W 05 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was monumented with a 2½" x 30" aluminum pipe with cap stamped as to location from the remains of both U.S. bearing trees. Specifically, the BLM field notes state that from the monument " a decayed hemlock stump, size indeterminate, bears S20°E, 65 lks. dist.; the fallen decayed trunk alongside has a small decayed blaze with no mks. visible" and " a hemlock stump hole, bears N20°W, 5 lks. dist. ". The BLM noted the following new bearing trees:

Hemlock 17 N31°E 56 lks. (36.96')
Presently alive and 23" in dia. having a healed lower blaze.
Set 7" spike W/side Measured N28°E 36.96'

Hemlock 17 S28°E 151½ lks. (99.99')
Presently alive and 24" in dia. having a healed lower blaze.
Measured S32°E (distance not verified)

Maple 21 S70°W 72 lks. (47.52')
Found Sugar Maple presently alive and 32" in dia. having a healed lower blaze.
Set 7" spike S/side Measured S65°W 46.95'

Hemlock 20 N61°W 102½ lks. (67.65')
Presently alive and 28" in dia. having an open lower blaze with scribing visible.
Set 7" spike N/side Measured N67°W 67.65'

C. Description of monument for corner and accessories established to perpetuate locating the position:

C-9; Section Corner common to Sections 19, 20, 29, and 30, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	SE/side	20" Sugar Maple	N59°E	21.24'
Set 7" spike	N/side	12" Sugar Maple	S62°E	25.69'
Set 7" spike	NE/side	12" Sugar Maple	N44°W	24.66'
		Location Post	South	1.0'

All of the new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	W/side	23" Hemlock	N28°E	36.96'
Set 7" spike	S/side	32" Sugar Maple	S65°W	46.95'
Set 7" spike	N/side	28" Hemlock	N67°W	67.65'

The above BLM new bearing trees were painted red.

SURVEY &
REMONUMENTATION

MAY 05 1987

COMMISSION