

SURVEY & REMONUMENTATION

MAY 05 1997 LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

| | | |
|---------------------------------------|---------------------------|---------------|
| <u>Baraga</u> | Located in: | Corner Code # |
| (County) | | |
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | C-10 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 13TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 698-699.

Relda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

C-10; One-quarter Corner common to Sections 29 and 30, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10; One-quarter Corner common to Sections 29 and 30, T51N, R33W;

Found the BLM monument 12 feet east of a fence to the south and 20 feet south of a fence to the east. From this monument a stump mound from a windthrown hemlock is located at record U.S. bearing and distance. Also from this monument a stump hole 18" in diameter is located at approximately U.S. bearing and distance. (Continued on back of form.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-10; One-quarter Corner common to Sections 29 and 30, T51N, R33W;

Found a 2 1/2" x 30" aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location.

| | | | | |
|-------------------|---------|-----------------|-------|--------|
| i) Set 7" spike | N/side | 8" Yellow Birch | S84°E | 19.92' |
| ii) Set 7" spike | SW/side | 8" Yellow Birch | S38°E | 36.96' |
| iii) Set 7" spike | SE/side | 6" Sugar Maple | S51°W | 25.70' |
| iv) Set 7" spike | S/side | 10" Red Maple | N57°W | 23.10' |
| | | Location Post | North | 1.0' |



(i) and (iii) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(ii) and (iv) are BLM new bearing trees and are further described in Part A. Both blazes as well as a band around the tree at the upper blaze are painted red.

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 5 Nov 1996

A. Description of original monument and accessories and/or subsequent restoration:

C-10; One-quarter Corner common to Sections 29 and 30, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Hemlock 14 S17°E 32 lks.

and a

Sugar 18 S65°W 8 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented with a 2½" x 30" aluminum pipe and cap at "record bearing and dist.; from the remains of the orig. bearing trees:

A hemlock stump hole, bears S. 17°E., 32 lks. dist.

A stump hole, bears S. 65°W., 8 lks. dist." And " from this cor., an iron pipe, ¾ in. diam., firmly set, projecting 12 ins. above the ground, bears N. 18°40.6' W., 0.469 chs. dist."

The BLM noted the following new bearing trees:

Yellow Birch 7 S37°E 56 lks. (36.96')
Presently alive and 8" in diameter with scribing visible in bark. Set a 7" spike on the SW/side.

Measured S38°E 36.96'

Maple 10 N56°W 35 lks. (23.10')
Found a red maple presently alive and 11" in diameter having a healed lower blaze. Set a 7" spike on the S/side.

Measured N57°W 23.10'

An iron pipe was recovered 20 November 1981 by Brian Taavola, P.S. #21583. A Land Corner Recordation Certificate filed by Mr. Taavola and recorded 19 February 1982 in Liber 4 page 19 states "Found: ¾" Iron pipe at approx. corner of old East & South fences".

Mr. Taavola noted the following accessories:

| | | |
|-------------|-------|--------|
| 7" Maple | N85°W | 7.88' |
| 6" Maple | N08°W | 14.90' |
| 5" Maple | N18°E | 3.95' |
| 5" Y. Birch | East | 7.40' |
| Face of 46" | East | 10.0' |
| Pine Stump | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-10; One-quarter Corner common to Sections 29 and 30, T51N, R33W;

The ¾" iron pipe recorded by Brian Taavola apparently has been removed. Its position as reestablished from the accessories bears approximately N44°W a distance of 18 feet from the BLM monument. From where Taavola's iron pipe was located a partially down cedar post fence bears to the south and 8 feet to the north this fence bears to the east. There is not a fence corner post. Rather the fence makes the corner around a 4-foot diameter pine stump. Accepted the BLM monument as marking the corner position. I did not remonument the corner but added "PA 345 1996" to the cap. Accepted as the best available evidence of the position of the original corner.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION