

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Baraga Located In: Corner Code #  
(County)

1. Public Land Survey T 51N R 33W C-11  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 716-717.

*Relda Mc Intyre*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-11; Section Corner common to Sections 29, 30, 31, and 32, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11; Section Corner common to Sections 29, 30, 31, and 32, T51N, R33W;

Found a copper rod with cap in a monument box as established by Brian Taavola, PS in 1981. The corner falls 9.0 feet north of the physical centerline of M-38. This corner was not remonumented. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11; Section Corner common to Sections 29, 30, 31, and 32, T51N, R33W;

Found a copper rod with a 1½" brass cap stamped "LLS 21583" 6 inches below the road surface and in a monument box.

Set 7" spike	NW/side	Power Pole	N67°E	142.79'
		Chiseled X on top	S02°E	103.40'
		of conc. R/W mon.		
Set 7" spike	N/side	Power Pole	S60°W	109.09'
Set 7" spike	SW/side	Power Pole	N49°W	81.41'

All of the above accessories are marked with a vertical red paint stripe.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*ML*  
12-18-96

Signed by Michael Mileski  
Surveyor's Michigan License No. 39091

Date 18 Dec 1996



A. Description of original monument and accessories and/or subsequent restoration:

C-11; Section Corner common to Sections 29, 30, 31, and 32, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Hemlock	12	S47°E	23 lks.
and a			
Hemlock	20	N39°W	22 lks.

This corner was reestablished in 1981 by Brian Taavola, PS #21583 "from Michigan Department of Transportation Plans dated 1956 file #N-23-A-3 and by prorating distances between section corners to west and east". Refer to LCRC prepared by Mr. Taavola and recorded in Liber 4 on page 18 of the Baraga County Land Corner Records. Mr. Taavola monumented the corner with a 1/2" copper rod with a 1 1/2" brass cap set inside of a monument box. He noted the following accessories:

Power Pole	N45°W	79.23'
8" Poplar	N05°E	82.14'
Top of R.O.W.	S05°E	103.23'
Marker		
NW Cor. Garage	S13°W	108.00'

Mr. Taavola's corner was accepted by the BLM during the course of their 1984 survey of T51N, R33W.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION