

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga  
(County)

Located In:

Corner Code #

- |   |                           |            |
|---|---------------------------|------------|
| 1. Public Land Survey                   | T <u>51N</u> R <u>33W</u> | <u>D-5</u> |
|   | T _____ R _____           | _____      |
|   | T _____ R _____           | _____      |
|   | T _____ R _____           | _____      |
| 2. Property Controlling<br>in Section   | S _____ T _____ R _____   | _____      |
|   | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous<br>Property in Section | S _____ T _____ R _____   | _____      |
|   | S _____ T _____ R _____   | _____      |
| 4. Lot No. _____, Recorded Plat _____   |                           |            |
| 5. Private Claims _____                 |                           |            |

RECEIVED FOR RECORD THIS 30TH DAY  
OF JULY 1996 AT 10:30 A.M. AND  
RECORDED IN LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGES  
643 - 644.

*Walter J. Schiller*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on July, 1996,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

D-5; One-quarter Corner common to Sections 8 and 17, T51N, R33W;

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*Walter J. Schiller*  
7-10-96

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5; One-quarter Corner common to Sections 8 and 17, T51N, R33W;

Found a 9/16" x 30" copperweld with cap stamped as to location as set by the BLM in 1984. This monument is located in the physical centerline of Bear Town Road which at this point is a north-south 16' wide gravel road. From this monument a 10" dia. cedar post projecting 68" above ground having a 16" vertical cut facing west and scribed "8/17 1/4 S, T51N, R33W, 16.5 W, CCCID" bears east a distance of 16.5 feet to the center. Replaced found copperweld with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap stamped as to location. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5; One-quarter Corner common to Sections 8 and 17, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 12 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

D-5; One-quarter Corner common to Sections 8 and 17, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Hemlock 12 N27°30'W 23 lks. and a Hemlock 26 N52°E 24 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented from a bearing accessory established in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service. The BLM recovered Mr. Hall's field notes of the "Carp River Truck Trail" at the Federal Records Center, Chicago, Illinois. A 6 inch diameter cedar post projecting 6 feet above the ground with the west face scribed "8/17 ¼ S, T51N, R33W, 16.5W, CCCID" was recovered and accepted as Mr. Hall's reference monument by the BLM. The BLM remonumented the corner with a 9/16" x 30" copperweld and cap stamped as to location and noted the following new bearing trees:

Maple 12 S70°E 93 lks. (61.38')

Found red maple presently alive and 16" in dia. having an open lower blaze with scribing visible.

Set 7" spike S/side Measured S74°E 60.61'

Maple 10 N83°W 67½ lks. (44.55')

Found red maple presently alive and 14" in dia. having an open lower blaze with scribing visible.

Set 7" spike S/side Measured N89°W 44.55'

C. Description of monument for corner and accessories established to perpetuate locating the position:

D-5; One-quarter Corner common to Sections 8 and 17, T51N, R33W;

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap stamped as to location 12 inches below the road surface.

Set 7" spike SW/side 12" Red Maple S51°E 48.75'

Set 7" spike SE/side 11" Red Maple S41°W 57.31'

Location Post East 15.3'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike S/side 16" Red Maple S74°E 60.61'

Set 7" spike S/side 14" Red Maple N89°W 44.55'

The above BLM new bearing trees were painted red.

SURVEY &  
REMONUMENTATION

MAY 05 1997

LIBER 4 PAGE 644

COMMISSION