

MAY 05 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga (County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 33W D-7
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 645 - 646.

Baraga County Register of Deeds

Register of Deeds Stamp & File Number

- 4. Lot No.
5. Private Claims

I, Michael Mileski, in a field survey on July, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-7; One-quarter Corner common to Sections 17 and 20, T51N, R33W;

See back of form.

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column D and row 7.

APPROVED LAND CORNER P.A. 345 OF 1990 Baraga County

Handwritten signature and date 7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-7; One-quarter Corner common to Sections 17 and 20, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. This monument is 0.5 feet west of a 10" dia. cedar post projecting 42" above ground having a 16" vertical cut facing north and scribed as to location. From this monument the centerline tangents of Bear Town Road extend to the north and to the east. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-7; One-quarter Corner common to Sections 17 and 20, T51N, R33W;

See back of form.



Signed by [Signature]

Date 13 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN, 1983

A. Description of original monument and accessories and/or subsequent restoration:

D-7; One-quarter Corner common to Sections 17 and 20, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch post witnessed by a

Fir 12 N83°W 10 lks. and a Cedar 10 N78°E 08 lks.

According to the field notes of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented at its original position in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service. The BLM recovered Mr. Hall's field notes of the "Carp River Truck Trail" at the Federal Records Center, Chicago, Illinois. A 6 inch diameter cedar post projecting 5 feet above ground with the northeast face scribed as to location was recovered and accepted as Mr. Hall's monument by the BLM during the previously mentioned survey of 1984. The BLM remonumented the corner with a 2½" x 30" aluminum pipe and cap stamped as to location and noted the following new bearing trees:

Spruce 9 S13°E 53½ lks. (35.31')  
Presently alive and 11" in dia. having a partially healed lower blaze with some scribing visible.

Set 7" spike E/side Measured S20°E 35.31'

Balsam Fir 6 N55°W 29 lks. (19.14')  
Presently alive and 10" in dia. having a healed lower blaze.  
Set 7" spike SW/side Measured N62°W 19.14'

C. Description of monument for corner and accessories established to perpetuate locating the position:

D-7; One-quarter Corner common to Sections 17 and 20, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	NE/side	6" Red Maple	S43°E	22.07'
Set 7" spike	S/side	6" Yellow Birch	S11°W	7.90'
Set 7" spike	S/side	8" Sugar Maple	S80°W	30.73'
		Location Post	North	1.0'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	E/side	11" Spruce	S20°E	35.31'
Set 7" spike	SW/side	10" Balsam Fir	N62°W	19.14'

The above BLM new bearing trees were painted red.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION