

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>R33W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 13TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 696-697.

Fields Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-9; One-quarter Corner common to Sections 20 and 29, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-9; One-quarter Corner common to Sections 20 and 29, T51N, R33W;

Accepted the BLM determination that the corner is lost. Found a 2 1/2" aluminum pipe with a 3 1/2" aluminum cap as set by the BLM in 1984 within 0.5 feet of its intended position. I did not remonument the corner but stamped the cap "PA 345 1996". Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9; One-quarter Corner common to Sections 20 and 29, T51N, R33W;

Found a 2 1/2" x 30" aluminum pipe with a 3 1/2" aluminum cap appropriately stamped as to location.

- | | | | | |
|-------------------|---------|---------------------|-------|--------|
| i) Set 7" spike | NW/side | 6" Red Maple | N65°E | 24.32' |
| ii) Set 7" spike | S/side | 10" Sugar Maple | S35°E | 43.22' |
| iii) Set 7" spike | E/side | 9" Dbl. Sugar Maple | S40°W | 11.22' |
| iv) Set 7" spike | N/side | 11" Yellow Birch | N52°W | 31.68' |
| | | Location Post | North | 1.0' |

(i) and (ii) are marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(iii) and (iv) are BLM new bearing trees and are further described in Part A.

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 5 Nov 1996

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
10-30-96



A. Description of original monument and accessories and/or subsequent restoration:

D-9; One-quarter Corner common to Sections 20 and 29, T51N, R33W;

Corner position originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and occupied by a yellow birch 20 inches in diameter witnessed by a Hemlock 18 N60°E 31 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between the section corners immediately to the east and to the west. The section corner to the west is a probable original corner and the section corner to the east is located in the center of a four-way road intersection. From the section corner to the east, a seasonal road extends approximately 1550 feet to the west. The centerline of this seasonal road at its westerly terminus lies 10 feet south of the reestablished section line. The BLM monumented this corner position with a 2½" x 30" aluminum pipe and cap and noted the following new bearing trees:

Double Maple	8	S46°W	17 lks. (11.22')
--------------	---	-------	------------------

Found a double sugar maple presently alive and 9" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the E/side.
Measured S40°W 11.22'

Yellow Birch	10	N48°W	48 lks. (31.68')
--------------	----	-------	------------------

Presently alive and 11" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the N/side.
Measured N52°W 31.68'

To each of the above BLM new bearing trees I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION