

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>D-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH
DAY OF DECEMBER, 1996 AT 10:30
A.M. AND RECORDED IN LIBER 4
OF LAND CORNER RECORDATION
RECORDS ON PAGES 718-719.

Nelda McAntyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11			●									
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-11; One-quarter Corner common to Sections 29 and 32, T51N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11; One-quarter Corner common to Sections 29 and 32, T51N, R33W;

Found a railroad spike as set by the BLM in 1984. Corner falls 5.0 feet north of the physical centerline of M-38. I did not remonument the corner. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11; One-quarter Corner common to Sections 29 and 32, T51N, R33W;

Found a railroad spike.

- | | | | | |
|-------------------|---------|-----------------|-------|---------|
| i) Set 7" spike | SE/side | Power Pole | N48°E | 98.03' |
| ii) Set 7" spike | SE/side | 8" Sugar Maple | S32°W | 96.40' |
| iii) Set 7" spike | NW/side | 10" Sugar Maple | S66°W | 132.59' |
| iv) Set 7" spike | S/side | Power Pole | N62°W | 141.20' |

(i) and (iv) are BLM accessories and are further described in Part A.
(ii) and (iii) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red.



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 18 Dec 1996

A. Description of original monument and accessories and/or subsequent restoration:

D-11; One-quarter Corner common to Sections 29 and 32, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a

Sugar 18 N25°W 16 lks.

Sugar 10 N87°E 47 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between government corners immediately to the east and west. The BLM monumented this position with a railroad spike witnessed by a

Power Pole N49°E 148½ lks. (98.01')

Set a 7" spike on the SE/side.

Measured N48°E 98.03'

Power Pole N58°W 214 lks. (141.24')

Set a 7" spike on the S/side.

Measured N62°W 141.20'

Each of the above BLM accessories were marked with a vertical red paint stripe.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION