

SURVEY & REMONUMENTATION

AUG 05 1994

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga
(County)

Located in: Corner Code #

- | | | |
|---------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | D-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. A RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 487.

Hilda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Dennis R. Destrampe in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

Post Original corner not found. A pipe was found 2/14/84 and recorded in Liber 4, Page 63. Land Corner Recordation.
Hemlock 16 N54E 16
Do 8 N6W 28

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

HJ
12-1-93

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

3/4" iron pipe as described in Liber 4, Page 63, Land Corner Recordation, found. Fit reasonably well with corner to west and east.

Witnesses found:

- 10" Red Maple N32E 1.83'
- 6" Red Maple S87E 23.14'
- 7" Red Maple S07E 14.88'
- 9" Y. Birch S65W 24.80'

All of the above bearing trees have nail & disk "RLS 24591" on face of tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" iron pipe with 1"X36" iron pipe with a 2 1/2" brass cap 6" above ground. Baraga Cty. Remonumentation brass cap stamped:

Witnesses:

- W face 10" Red Maple N32E 2.46' (Nail & tag "UPEA 18983" set)
- N face 6" Red Maple S87E 23.34' (Nail & tag "UPEA 18983" set)
- W face 7" Red Maple S07E 15.01' (Nail & tag "UPEA 18983" set)
- N face 9" Y. Birch S65W 25.09' (Nail & tag "UPEA 18983" set)

SC
T51N R33W
1/4 S32
1994

Signed by Dennis R. Destrampe Date June 24, 1994

Surveyor's Michigan License No. 18983