

**SURVEY &
RECORDATION**

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located In:

Corner Code #

- | | | |
|--------------------------------------|---------------------------|-------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | E-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 647 - 648.

Allen G. Philbrook
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on July, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner common to Sections 4 and 5, T51N, R33W;

See back of form.

| | | | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

7/10
7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1; Closing Corner common to Sections 4 and 5, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. From this monument the exposed root system of a yellow birch growing over a severely decayed stump bears S62°W a distance of 27.0 feet. Also from this monument a 10" dia. cedar post projecting 3 feet above ground having a 16" vertical cut on its southeast face marked as described in Part A bears west a distance of 0.8 feet to center. The centerline tangents of Bear Town Road extend to the east and to the south. I left the BLM monument in place and stamped the cap "PA 345 1996".

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1; Closing Corner common to Sections 4 and 5, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 10 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner common to Sections 4 and 5, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch post witnessed by a

Fir 12 S57°E 49 lks. and a Hemlock 16 S62°W 41 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, a 6 inch diameter cedar post projecting 5 feet above ground with the south face erroneously scribed " 32 / 33 / 5 / 4, T51N, R33W, CCCID " as set in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service was found and accepted. The BLM recovered Mr. Hall's field notes of the "Carp River Truck Trail" survey at the Federal Records Center, Chicago, Illinois. The BLM field notes state that Mr. Hall's monument was in agreement with the hemlock U.S. bearing tree and with the remains of a 1935 bearing tree. The BLM remonumented the corner with a 2½" x 30" aluminum pipe with cap stamped as to location and noted the following new bearing trees:

White Pine 15 S04°E 144½ lks. (95.37')
Found standing dead and 20" in dia. having an open lower blaze with scribing visible.
Measured S09°E 95.0' to center

Yellow Birch 10 S27°W 63 lks. (41.58')
Presently alive and 12" in dia. having an open lower blaze with scribing visible.
Set 7" spike W/side Measured S24°W 41.88'

C. Description of monument for corner and accessories established to perpetuate locating the position:

E-1; Closing Corner common to Sections 4 and 5, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984. Accepted as a careful and faithful perpetuation of position of the original corner.

| | | | | |
|--------------|--------|------------------|-------|--------|
| Set 7" spike | N/side | 15" Red Maple | S83°E | 26.16' |
| Set 7" spike | E/side | 10" Red Maple | S13°E | 72.89' |
| Set 7" spike | S/side | 13" Red Maple | N89°W | 38.95' |
| Set 7" spike | W/side | 10" Yellow Birch | N15°W | 24.65' |
| | | Location Post | South | 1.0' |

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION