

**SURVEY &
REMONUMENTATION**

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga
(County)

Located In:

Corner Code #

- | | | |
|---------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | <u>E-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 649 - 650.

John J. Billard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on July, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
E-3; Section Corner common to Sections 4, 5, 8, and 9, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a sugar maple post witnessed by a Sugar 14 S__W (?) 13 lks. and a Hemlock 12 N__E (?) 31 lks.
Continued on back of page

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-3; Section Corner common to Sections 4, 5, 8, and 9, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. From this monument a 10" diameter cedar post projecting 5½ feet above ground having a 15" vertical cut scribed as to location bears N35°E a distance of 1.9 feet to center. Also from this monument the centerline tangents of Bear Town Road extend to the north and to the west. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-3; Section Corner common to Sections 4, 5, 8, and 9, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 13 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
JK
7-10-96

A. Description of original monument and accessories and/or subsequent restoration:

E-3; Section Corner common to Sections 4, 5, 8, and 9, T51N, R33W;

According to the field notes of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented at its original position in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service. The BLM recovered Mr. Hall's field notes of the "Carp River Truck Trail" survey at the Federal Records Center, Chicago, Illinois. The BLM recovered a 2" diameter iron pipe in agreement with Mr. Hall's 1935 bearing accessories. Namely,

Cedar Post, 6" in diameter, scribed as to location on NW face, bears N45°E, 3 lks. dist.

Sugar Maple stump hole N88°E 27½ lks.

The BLM remonumented the corner with a 2½" x 30" aluminum pipe and cap stamped as to location and noted the following new bearing trees:

Maple 11 N24°E 65 lks. (42.90')

Found sugar maple presently alive and 16" in dia. having a mostly healed lower blaze with some scribing visible.

Set 7" spike W/side Measured N18°E 42.90'

Yellow Birch 7 S48°E 10 lks. (6.60')

Presently alive and 10" in dia. having an open lower blaze with scribing visible.

Set 7" spike S/side Measured S52°E 6.60'

Yellow Birch 10 S65°W 91 lks. (60.06')

Presently alive and 15" in dia. having an open lower blaze with scribing visible.

Set 7" spike N/side Measured S60°W 60.06'

Maple 7 N37°W 39 lks. (25.74')

Found Sugar Maple presently alive and 9" in dia. having a healed lower blaze.

Set 7" spike SW/side Measured N44°W 25.74'

C. Description of monument for corner and accessories established to perpetuate locating the position:

E-3; Section Corner common to Sections 4, 5, 8, and 9, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as by the BLM in 1984.

Set 7" spike N/side 13" Sugar Maple S90°E 31.03'

Set 7" spike W/side 9" Sugar Maple S05°W 27.22'

Location Post N40°E 1.0'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike W/side 16" Sugar Maple N18°E 42.90'

Set 7" spike S/side 10" Yellow Birch S52°E 6.60'

Set 7" spike N/side 15" Yellow Birch S60°W 60.06'

Set 7" spike SW/side 9" Sugar Maple N44°W 25.74'

The above BLM new bearing trees were painted red.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION