

MAY 05 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga Located In: Corner Code #  
(County)

1. Public Land Survey T 51N R 33W E-6  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

RECEIVED FOR RECORD THIS 30TH DAY  
OF JULY 1996 AT 10:30 A.M. AND  
RECORDED IN LIBER 4 OF LAND CORNER  
RECORDATION RECORDS ON PAGES  
651 - 652.

*Walter J. Billard*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on July, 19 96,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current  
manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and  
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a  
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found  
as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

E-6; One-quarter Corner common to Sections 16 and 17, T51N, R33W;

See back of form.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*WJ*  
7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6; One-quarter Corner common to Sections 16 and 17, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. From this  
monument a 22" cedar stump bears S09°W a distance of 25 lks. and a very dim stump  
hole bears N37°W a distance of 18 lks. as stated by the BLM. I left the BLM monument  
in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful  
perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6; One-quarter Corner common to Sections 16 and 17, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 12 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

E-6; One-quarter Corner common to Sections 16 and 17, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar 12 S09°W 25 lks. and a Fir 12 N37°W 18 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented with a 2½" x 30" aluminum pipe with cap stamped as to location from the remains of both U.S. bearing trees. Specifically, the BLM field notes state that from the monument " a cedar stump, 22 ins. diam., bears S9°W, 25 lks. dist., the fallen trunk alongside has a decayed open blaze with no mks. visible" and " a fir stump hole, bears N37°W, 18 lks. dist.". The BLM noted the following new bearing trees:

Maple 6 S57°E 18 lks. (11.88')  
Found sugar maple presently alive and 10" in dia. having a partially healed lower blaze with scribing visible.

Set 7" spike S/side Measured S63°E 11.88'

Cedar 5 N66°W 81½ lks. (53.79')  
Presently alive and 8" in dia. having an open lower blaze with scribing visible.

Set 7" spike N/side Measured N70°W 53.79'

C. Description of monument for corner and accessories established to perpetuate locating the position:

E-6; One-quarter Corner common to Sections 16 and 17, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	W/side	10" Sugar Maple	N02°E	23.02'
Set 7" spike	N/side	11" White Spruce	N78°E	25.65'
Set 7" spike	NW/side	12" Red Maple	S35°W	18.09'
		Location Post	East	1.2'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	S/side	10" Sugar Maple	S63°E	11.88'
Set 7" spike	N/side	8" Cedar	N70°W	53.79'

The above BLM new bearing trees were painted red.

SURVEY &  
REMONUMENTATION

MAY 05 1987

COMMISSION

LIBER 4 PAGE 652