

**SURVEY &
REMONUMENTATION**

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION
Baraga

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 33W E-7
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 30TH DAY OF JULY 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 653 - 654.

Theda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael Mileski, in a field survey on July, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T51N, R33W;

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

[Signature]
7-10-96

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T51N, R33W;

Recovered the BLM monument and all accessories as described in Part A. This monument is at the southwest face of a 10" dia. cedar post projecting 40" above ground having a 15" vertical cut facing southwest scribed as to location. From this monument the centerline tangents of Bear Town Road extend to the south and to the west. I left the BLM monument in place and stamped the cap "PA 345 1996". Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T51N, R33W;

See back of form.



Signed by *Michael Mileski*

Date 13 July 1996

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a spruce post witnessed by a

Cedar 12 S74°W 10 lks. and a Hemlock 20 N27°E 16 lks.

According to the field notes of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented at its original position in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service. The BLM recovered Mr. Hall's field notes of the "Carp River Truck Trail" survey at the Federal Records Center, Chicago, Illinois. A 6 inch diameter cedar post projecting 5½ feet above the ground with the SW face scribed as to location was recovered and accepted as Mr. Hall's monument by the BLM. The BLM remonumented the corner with a 2½" x 30" aluminum pipe and cap stamped as to location and noted the following new bearing trees:

Yellow Birch 6 N02°E 22½ lks. (14.85')
Presently alive and 9" in dia. having an open lower blaze with scribing visible.
Set 7" spike E/side Measured N03°W 14.85'

Yellow Birch 11 S89°E 87 lks. (57.42')
Presently alive and 13" in dia. having an open lower blaze with scribing visible.
Set 7" spike S/side Measured N89°E 56.89'

Spruce 7 S32°W 22 lks. (14.52')
Found white spruce presently alive and 14" in dia. having a healed lower blaze.
Set 7" spike E/side Measured S26°W 14.52'

Maple 6 N40°W 61 lks. (40.26')
Found red maple presently alive and 8" in dia. having an open lower blaze with scribing visible.
Set 7" spike NE/side Measured N48°W 40.26'

C. Description of monument for corner and accessories established to perpetuate locating the position:

E-7; Section Corner common to Sections 16, 17, 20, and 21, T51N, R33W;

Found 2½" dia. aluminum pipe with 3" aluminum cap appropriately stamped as to location as set by the BLM in 1984.

Set 7" spike	E/side	8" Red Maple	N04°E	22.31'
Set 7" spike	S/side	10" Red Maple	N66°E	25.76'
Set 7" spike	N/side	8" Red Maple	S59°E	10.99'
		Location Post	West	1.0'

All of the above new bearing trees are marked with upper and lower blazes, scribed "NBT", and painted red.

The following new bearing trees were established by the BLM in 1984. The condition of each is described in Part A.

Set 7" spike	E/side	9" Yellow Birch	N03°W	14.85'
Set 7" spike	S/side	13" Yellow Birch	N89°E	56.89'
Set 7" spike	E/side	14" White Spruce	S26°W	14.52'
Set 7" spike	NE/side	8" Red Maple	N48°W	40.26'

The above BLM new bearing trees were painted red.

SURVEY
MONUMENT
MAY 05 1985
COMM.