

**SURVEY &  
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>E-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 23RD  
DAY OF OCTOBER, 1996 AT 10:30  
A.M. AND RECORDED IN LIBER 4  
OF LAND CORNER RECORDATION  
RECORDS ON PAGES 670-671.

*Helda McAnis*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on October, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	13		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-8; One-quarter Corner common to Sections 20 and 21, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8; One-quarter Corner common to Sections 20 and 21, T51N, R33W;

Found the 9/16" x 30" copperweld as set by the BLM in 1984 at the road surface and in agreement with the BLM new bearing trees. From this monument a partially standing cedar post fence bears east. This monument is located 7 feet east of the physical centerline of Bear Town Road which at this point is a north-south, 20 foot wide, graded gravel road. Replaced found copperweld with a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8; One-quarter Corner common to Sections 20 and 21, T51N, R33W;

Set a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location 12" below the road surface.

- |                   |         |                    |       |         |
|-------------------|---------|--------------------|-------|---------|
| i) Set 7" spike   | SE/side | 10" Twin Red Maple | N24°E | 85.32'  |
| ii) Set 7" spike  | S/side  | 11" Red Oak        | N61°E | 36.96'  |
| iii) Set 7" spike | SW/side | 11" Red Oak        | S52°E | 41.95'  |
| iv) Set 7" spike  | SE/side | 22" Red Oak        | S44°W | 108.41' |
| v) Set 7" spike   | NE/side | 18" Red Oak        | N50°W | 121.88' |
|                   |         | Location Post      | N87°E | 26.8'   |



(ii) is a BLM new bearing tree and is further described in Part A.

(i), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze are painted red.

Signed by *Michael Mileski*  
Surveyor's Michigan License No. 39091

Date 22 Oct 1996

A. Description of original monument and accessories and/or subsequent restoration:

E-8; One-quarter Corner common to Sections 20 and 21, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock      28      S43°W      45 lks.

and a

Hemlock      20      N62°E      28 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was remonumented with a 9/16" x 30" copperweld from a bearing accessory established in 1935 by Marshall J. Hall, Junior Engineer, U.S. Indian Service. The BLM field notes state that

"The ¼ sec. cor. of secs. 20 and 21, determined at record bearing and dist.; from the remains of a 1935 bearing accessory:

The base of a cedar post, 6 ins. diam., firmly set, flush with the ground, for a reference monument, bears East, 25 lks. dist., with no mks. visible.

This cor. was set at the cor. position called for by Marshall J. Hall, Junior Engineer, U.S. Indian Service, in 1935, according to his field notes of "Carp River Truck Trail" recovered at the Federal Records Center, Chicago, Illinois. There is no remaining evidence of the orig. cor.; however, this position is harmoniously related to existing orig. cors., and is accepted as the best available evidence of the orig. cor. position."

The BLM noted the following new bearing trees:

Oak            7            N67°E            56 lks. (36.96')

Found a red oak presently alive and 11" in diameter having a healed lower blaze. I added an upper blaze and painted both blazes red as well as painted a red band around the tree at the upper blaze.

Set 7" spike    S/side            Measured      N61°E            36.96'

and an

Aspen        10        S89°W        70 lks. (46.20')

Destroyed due to logging operations.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION