

**SURVEY &
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

COMMISSION

Baraga
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|----------------------------|------------|
| 1. Public Land Survey | T <u>51N</u> R <u>R33W</u> | <u>E-9</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 23RD DAY OF OCTOBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 668-669.

Thelma McAntone
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on October, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9					●								
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-9; Section Corner common to Sections 20, 21, 28, and 29, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-9; Section Corner common to Sections 20, 21, 28, and 29, T51N, R33W;

Found a small p-k nail in the center of an asphalt intersection in agreement with the remaining Taavola accessories. From this point the physical centerline of a graded gravel road bears north, the physical centerline of an asphalt road bears east, the physical centerline of an asphalt road bears south, and the physical centerline of a seasonal road bears west. Replaced the p-k nail with a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap set inside a monument box. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-9; Section Corner common to Sections 20, 21, 28, and 29, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location inside a monument box.

- | | | | | |
|-------------------|---------|-----------------|-------|---------|
| i) Set 7" spike | NW/side | 12" White Ash | N43°E | 140.91' |
| ii) Set 7" spike | NE/side | 10" Aspen | S54°E | 85.80' |
| iii) Set 7" spike | E/side | Power Pole | S10°W | 130.06' |
| iv) Set 7" spike | N/side | Power Pole | S71°W | 74.83' |
| v) Set 7" spike | S/side | 12" White Birch | N69°W | 53.30' |

(i) and (ii) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze are painted red.

(iii) is not marked.

(iv) and (v) are existing Taavola accessories and are further described in Part A.



Signed by Michael Mileski

Date 22 OCT 1996

Surveyor's Michigan License No. 39091

LIBER 4 PAGE 668

A. Description of original monument and accessories and/or subsequent restoration:

E-9; Section Corner common to Sections 20, 21, 28, and 29, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch post witnessed by a

Sugar 12 S55°E 14 lks.

and a

Hemlock 14 N32°W 38 lks.

According to a Land corner Recordation Certificate filed by Brian Taavola, P.S. 21583 of the Michigan Department of Transportation and recorded 19 February 1982 in Liber 4 page 17 a "3/4" Iron pin with rectangular head at intersection of East-West & North-South County Roads" was recovered and accepted. Mr. Taavola noted the following accessories:

9" Tri. Maple S23°E 79.82'
Gone. Apparently removed during road improvement / construction.

Power Ser. Pole S70°W 74.85'
Set 7" spike directly below a double-headed nail and MDOT tag on the N/side.
Measured S71°W 74.83'

7" W. Birch N70°W 53.33'
Presently alive and 12" in diameter.
Set 7" spike directly below an overgrown double-headed nail and MDOT tag on the S/side.
Measured N69°W 53.30'

This monument was also accepted by the Bureau of Land Management during the course of a survey conducted by Stephen Douglas from 10 May 1984 to 10 November 1984 and approved 23 September 1985. The BLM field notes state the following:

"The cor. of secs. 20, 21, 28, and 29, recorded by Brian R. Taavola, Michigan Department of Transportation, R.L.S. No. 21583, in 1981, monumented with an iron bar, 3/4 in. sq., firmly set, 6 ins. below the surface, in the center of the intersection of graded gravel roads, bears N., E. and S., and a woods road, bears W. There is no remaining evidence of the orig. cor.; however, this position is harmoniously related to existing orig. cors., has long been recognized by local surveyors and adjacent landowners, and is accepted as the best available evidence of the orig. cor. position."

The BLM did not remonument the corner nor note any accessories.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION