

**SURVEY &  
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in MAY 05 1997

Baraga ~~COMMISSION~~ Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey      T 51N R 33W      E-10 \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

RECEIVED FOR RECORD THIS 13TH DAY OF NOVEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 694-695.

*Helda Mc Intyre*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-10; One-quarter Corner common to Sections 28 and 29, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-10; One-quarter Corner common to Sections 28 and 29, T51N, R33W;

Corner position falls 2.3 feet west of the physical centerline of a north-south asphalt road. At the N 1/16 corner an old and partially down fence bears to the east and to the west. At the S 1/16 corner a fence bearing to the east is located approximately 8 feet south. (Continued on back of form.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-10; One-quarter Corner common to Sections 28 and 29, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap appropriately stamped as to location in a monument box.

|                   |         |               |       |        |
|-------------------|---------|---------------|-------|--------|
| i) Set 7" spike   | W/side  | Power Pole    | N32°E | 43.56' |
| ii) Set 7" spike  | N/side  | 8" Spruce     | N49°E | 37.90' |
| iii) Set 7" spike | NE/side | 12" Hemlock   | S46°E | 68.12' |
| iv) Set 7" spike  | S/side  | 12" Aspen     | S82°W | 44.95' |
| v) Set 7" spike   | SW/side | Power Pole    | N43°W | 50.63' |
|                   |         | Location Post | West  | 35.0'  |

(i) is a BLM accessory to which a vertical red paint stripe at shoulder height was added and is further described in Part A.

(ii), (iii), and (iv) are marked with an upper and lower blaze. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(v) is marked with a vertical red paint stripe at approximately shoulder height.

| A  | B  | C | D  | E | F  | G | H  | I | J  | K | L  | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

10-30-96

Signed by *Michael Mileski*  
Surveyor's Michigan License No. 39091

Date 5 Nov 1996

LIBER **4** PAGE **694**



A. Description of original monument and accessories and/or subsequent restoration:

E-10; One-quarter Corner common to Sections 28 and 29. T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a yellow birch post witnessed by a

Sugar 18 S20°W 6 lks.

and a

Sugar 8 N12°E 26 lks.

This corner was considered lost and reestablished midway and on line between the section corners immediately to the north and to the south by the Bureau of Land Management during the course of a survey conducted by Stephen Douglas from 10 May 1984 to 10 November 1984 and approved 23 September 1985. According to the BLM field notes, this position falls in the center of a north-south graded gravel road. The BLM set a 9/16" x 30" copperweld and noted the following accessories:

Power Pole N30°E 66 lks. (43.56')  
Set a 7" spike directly below a small nail on the W/side  
Measured N32°E 43.56'

Power Pole N33°W 66½ lks. (43.89')  
Gone.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a ½" x 28" iron rod set vertically over the BLM copperweld. Replaced the found iron rod with a 1"(I.D.) x 36" galvanized iron pipe with a 2" aluminum cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

SURVEY &  
REMONUMENTATION

MAY 05 1987

COMMISSION