

**SURVEY &
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in * **COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>E-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 726-727.

Relda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12; One-quarter Corner common to Sections 32 and 33, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12; One-quarter Corner common to Sections 32 and 33, T51N, R33W;

Found a 1/2" x 24" copper rod and plastic cap stamped "MDOT 21583" in a monument box set over a 1 3/4" iron pipe 20 inches below the road surface. Corner falls in the center of a four-way road intersection. Replaced the copper rod with a 1"(I.D.) x 18" galvanized iron pipe and cap. Accepted as a the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12; One-quarter Corner common to Sections 32 and 33, T51N, R33W;

Set a 1"(I.D.) x 18" galvanized iron pipe with a 2" aluminum cap inside of an existing monument box.

i) Set 7" spike	NW/side	11" Sugar Maple	N47°E	98.82'
ii) Set 7" spike	SW/side	4" Red Maple	S64°E	88.81'
iii) Set 7" spike	NE/side	10" Red Maple	S49°E	109.73'
iv) Set 7" spike	SW/side	8" Red Maple	S38°E	116.76'
v) Set 7" spike	W/side	Power Pole	S15°W	156.40'
vi) Set 7" spike	N/side	Power Pole	S74°W	103.06'
vii) Set 7" spike	SW/side	Power Pole	N35°W	57.25'

- (i) and (ii) are MDOT new bearing trees and are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red.
- (iii) is marked in the same manner as (i) and (ii).
- (iv) is not marked.
- (v) and (vii) are marked with a vertical red paint stripe.
- (vi) is an MDOT accessory and is marked with a vertical red paint stripe.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32	●	33		34		35		36	
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

ML
12-18-96



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 18 Dec 1996
LIBER 4 PAGE 726

A. Description of original monument and accessories and/or subsequent restoration:

E-12; One-quarter Corner common to Sections 32 and 33, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a hemlock post witnessed by a

Sugar	10	S82°W	12 lks.
Hemlock	24	N38°E	12 lks.

This corner was recovered in 1981 by Brian Taavola, PS #21583. Mr. Taavola found this corner to be monumented with a "½" Iron pipe 1.5 feet south of Lindblom Road and on line with North-South fence." The following accessories were established:

4" Maple	N25°W	49.59'
7" Spruce	N25°E	41.75'
Power Pole	S05°W	30.17'
11" Maple	S50°E	44.18'

Mr. Taavola remonumented the corner with a ½" rod with a 1½" brass cap placed in a monument box. Refer to LCRC prepared by Mr. Taavola and recorded in Liber 4 on page 15 of Baraga County Land Corner Records.

In 1991 Mr. Taavola re-recorded this corner indicating that "Corner was witnessed before the beginning of the road construction project and later reset from the wits with a 5/8" copper clad rod with a yellow plastic cap stamped MDOT 21583 in a monument box." The following witnesses were noted:

S75°W	102.99'	Power Pole
S62°E	88.87'	4" Maple
S35°E	116.68'	8" Maple
N50°E	98.85'	10" Maple

Refer to LCRC prepared by Mr. Taavola and recorded in Liber 4 on page 226 of Baraga County Land Corner Records.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION