

AUG 05 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>E-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. A RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 486.

Nelda J. Robillard
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Dennis R. Destrampe in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post Original corner not found. Re-established 4/23/76, recorded Liber 1, Page 268; recovered 2/14/84, recorded Liber 4, Page 63; re-set 5/21/91, recorded Liber 4, Page 227, Land Corner Recordation.
 Maple 10 N47E 28
 Birch 10 N42W 20

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found corner as recorded in Liber 4, Page 227. 5/8" copper clad rod with yellow plastic cap stamped MDOT 21583 in monument box at intersection of Wadaga Road and prison access road.

Witnesses found: MDOT reference tag & nail in c/1 of tree.

S65W 71.50' Power Pole
 N68E 121.09' 10" W. Pine
 N37E 124.17' 7" Maple

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

[Signature]
12-1-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner accepted as found.

Witnesses:

7" Maple N32E 124.16' (MDOT tag & nail found)
 10" W. Pine N63E 121.09' (MDOT tag & nail found)
 Power Pole S67W 71.52' (MDOT tag & nail found)
 23" Hemlock N38W 229.71' (Nail & tag "UPEA 18983" set, scribed "NBT")



Signed by Dennis R. Destrampe Date June 17, 1994
 Surveyor's Michigan License No. 18983