

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	F-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 728-729.

*Helda M. Antyca*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-1; North One-quarter Corner Section 4, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1; North One-quarter Corner Section 4, T51N, R33W;

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*[Signature]*  
12-18-96

Recovered the BLM monument as set in 1984. The position of the BLM monument was verified by a traverse. Replaced the BLM copperweld with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap. Corner is located 3 feet north of the physical centerline of Bear Town Road which at this point is a 15 foot wide gravel road bearing east and west. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1; North One-quarter Corner Section 4, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location 12 inches below the road surface.

i)	Set 7" spike	SW/side	15" Hemlock	S39°E	81.18'
ii)	Set 7" spike	SE/side	10" Sugar Maple	S48°W	54.78'
iii)	Set 7" spike	NE/side	20" Hemlock	N60°W	40.18'
iv)	Set 7" spike	SW/side	20" Hemlock	N32°W	64.67'
v)			S ¼ Cor. Sec.33	East	3.23'
vi)			Location Post	South	19.0'



(i) and (ii) are BLM new bearing trees and are further described in Part A.

(iii) and (iv) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(v) The S ¼ cor. sec. 33, T52N, R33W is monumented with a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location placed 12 inches below the road surface.

Signed by *[Signature]*  
Surveyor's Michigan License No. 39091

Date 18 Dec 1996  
LIBER 4 PAGE 728

A. Description of original monument and accessories and/or subsequent restoration:

F-1; North One-quarter Corner Section 4, T51N, R33W;

This corner was not monumented during the U.S. Survey.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished on the standard line midway between the closing corners immediately to the east and west. The BLM monumented this position with a 9/16" x 30" copperweld and cap witnessed by a

Hemlock	13	S34°E	123 lks. (81.18')
Presently alive and 15" in diameter having a healed lower blaze.			
Set a 7" spike on the SW/side.			
Measured		S39°E	81.18'

and a

Maple	10	S50°W	83½ lks. (55.11')
Found an alive sugar maple 10" in diameter having a partially healed lower blaze with scribing visible.			
Set a 7" spike on the SE/side.			
Measured		S48°W	54.78'

To each of the above BLM new bearing trees, I added an upper blaze. Both blazes as well as a band around the tree at the upper blaze were painted red.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION