

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>F-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 734-735.

*Relda McIntyre*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-11; One-quarter Corner common to Sections 28 and 33, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-11; One-quarter Corner common to Sections 28 and 33, T51N, R33W;

Found a 1" diameter iron rod in a monument box as recovered by Brian Taavola, PS in 1981. The corner is located 14.0 feet north of the physical centerline of M-38. This corner was not remonumented. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11; One-quarter Corner common to Sections 28 and 33, T51N, R33W;

Found a 1" iron rod in a monument box.

Set 7" spike	SE/side	Power Pole	N55°E	45.95'
Set 7" spike	SW/side	Power Pole	S73°E	146.01'
Set 7" spike	W/side	Power Pole	S18°W	54.50'
Set 7" spike	E/side	Power Pole	N31°W	29.80'

All of the above accessories are marked with a vertical red paint stripe.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*[Signature]*  
12-18-96



Signed by *[Signature]*  
Surveyor's Michigan License No. 39091

Date 18 Dec 1996

A. Description of original monument and accessories and/or subsequent restoration:

F-11; One-quarter Corner common to Sections 28 and 33, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a cedar post witnessed by a

Cedar	7	N59°W	14 lks.
Hemlock	8	N36°E	25 lks.

This corner was recovered in 1981 by Brian Taavola, PS #21583 as being monumented with a 1" iron pin in a monument box as per Michigan Department of Transportation Plans, File #N-23-A-3, 1956. Refer to LCRC prepared by Mr. Taavola and recorded in Liber 4 on page 14 of the Baraga County Land Corner Records. Mr. Taavola did not remonument the corner but noted the following accessories:

Tel. Pole	S15°W	54.53'
Power Pole	N60°E	45.93'
Power Pole	N30°W	29.84'
7" Spruce	S35°E	70.93'

Mr. Taavola's corner was accepted by the BLM during the course of their 1984 survey of T51N, R33W.

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION