

**SURVEY &
REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in
COMMISSION
Baraga
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH
DAY OF DECEMBER, 1996 AT 10:30
A.M. AND RECORDED IN LIBER 4
OF LAND CORNER RECORDATION
RECORDS ON PAGES 736-737.

Relda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Closing Corner common to Sections 3 and 4, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1; Closing Corner common to Sections 3 and 4, T51N, R33W;

This corner was reestablished on line and at proportionate distance between standard corners immediately to the east and west. Corner position falls in the centerline of a railroad 2.4 feet west of the east rail and 4.5 feet north of the physical centerline of Bear Town Road which at this point is an 18 foot wide, gravel road bearing east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1; Closing Corner common to Sections 3 and 4, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap stamped as to location 18" below the road surface.

- | | | | | | |
|------|--------------|---------|------------------|-------|---------|
| i) | Set 7" spike | NW/side | 14" White Spruce | N38°E | 123.75' |
| ii) | | NW cor. | RR X-ing sign | S46°E | 22.60' |
| iii) | Set 7" spike | N/side | Power Pole | S74°W | 123.17' |
| iv) | Set 7" spike | N/side | 12" Red Maple | N80°W | 75.18' |
| v) | | | S.C.Sec. 33 & 34 | East | 15.27' |

(i) and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red.

(v) The standard corner of sections 33 and 34, T52N, R33W is monumented with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap stamped as to location.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

[Signature]
12-18-96



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 18 Dec 1996

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Closing Corner common to Sections 3 and 4, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Meilen, D.S. in 1845 and monumented with a wood post witnessed by a

Fir	8	S41°E	47 lks.
Yellow Birch	18	S10°W	32 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost. The BLM neither found nor set a monument.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION