

**SURVEY &
REMONUMENTATION**

FEB 23 1998

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> SECTION	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 31ST DAY OF DECEMBER A.D. 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 811-812

Fields Bishop

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on 22 October, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9	●	10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4; One-quarter Corner common to Sections 9 and 10, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4; One-quarter Corner common to Sections 9 and 10, T51N, R33W;

Found a 2½" diameter aluminum pipe and cap as set by the BLM in 1984. The position of this monument was verified by a traverse. I did not remonument the corner, but stamped "PA 345 1997" to the cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4; One-quarter Corner common to Sections 9 and 10, T51N, R33W;

Found a 2½" diameter aluminum pipe with a 3" aluminum cap stamped as to location projecting 6" above ground.

i)	Set 7" spike	W/side	8" Hemlock	N15°E	12.75'
ii)	Set 7" spike	SW/side	17" Yellow Birch	S20°E	16.50'
iii)	Set 7" spike	W/side	9" Cedar	S36°W	13.86'
iv)	Set 7" spike	SW/side	12" White Birch	N29°W	18.93'
			6" Steel fence post w/ yellow sign	North	1'

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

10-24-97
ML

(i) and (iv) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes and a band around the tree at the upper blaze were painted red.

(ii) and (iii) are BLM new bearing trees and are further described in Part A.



LIBER 4 PAGE 811

Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 23 Dec 1997

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

G-4; One-quarter Corner common to Sections 9 and 10, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a spruce post witnessed by a

Cedar 6 S68°W 21 lks.

and a

Cedar 12 N55°E 06 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between government corners immediately to the north and south. Mr. Douglas monumented the corner with a 2½" x 30" aluminum pipe and cap witnessed by a

Yellow Birch 16 S16°E 25 lks. (16.50')

Presently alive and 17" in diameter having a partially healed lower blaze with scribing visible.

Set 7" spike SW/side Measured S20°E 16.50'

Cedar 7 S39°W 21 lks. (13.86')

Presently alive and 9" in diameter having a partially healed lower blaze with scribing visible.

Set 7" spike W/side Measured S36°W 13.86'

To each of the above new bearing trees, I added an upper blaze. Both blazes and a band around the tree at the upper blaze were painted red.