

SURVEY & REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

MAY 05 1997

For corners in

COMMISSION
Baraga
 (County)

Located In: _____ Corner Code # _____

- | | | |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey | T <u>51N</u> R <u>33W</u> | <u>G-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 740-741.

Relda McAnty
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6; One-quarter Corner common to Sections 15 and 16, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6; One-quarter Corner common to Sections 15 and 16, T51N, R33W;

Found a 2½" diameter aluminum pipe with a 3" aluminum cap projecting 8 inches above the ground as set by the BLM in 1984. The position of this monument was verified by a traverse. I did not remonument the corner, but stamped "PA 345 1996" to the cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6; One-quarter Corner common to Sections 15 and 16, T51N, R33W;

Found a 2½" diameter aluminum pipe with a 3" aluminum cap stamped as to location projecting 8 inches above the ground.

- | | | | | | |
|------|--------------|--------|-----------------|-------|--------|
| i) | Set 7" spike | E/side | 5" Red Maple | N20°E | 39.65' |
| ii) | Set 7" spike | N/side | 12" Cedar | N78°E | 19.80' |
| iii) | Set 7" spike | W/side | 4" White Spruce | S27°W | 72.72' |
| iv) | Set 7" spike | N/side | 6" Sugar Maple | N79°W | 72.83' |
| v) | | | Location Post | North | 1.0' |

(i), (iii), and (iv) are marked with with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

(ii) is a BLM new bearing tree and is further described in Part A.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

JK
12-18-96



Signed by *Michael Mileski*
 Surveyor's Michigan License No. 39091

Date 18 Dec 1996

A. Description of original monument and accessories and/or subsequent restoration:

G-6; One-quarter Corner common to Sections 15 and 16, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a cedar post witnessed by a

Fir	10	N45°E	42 lks.
and a Cedar	12	N83°W	12 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was considered lost and reestablished midway and on line between government corners immediately to the north and south. The BLM monumented this position with a 2½" x 30" aluminum pipe and cap witnessed by a

Cedar	11	N76°E	30 lks. (19.80')
-------	----	-------	------------------

Presently alive and 12" in diameter having a partially healed lower blaze with scribing visible. Set a 7" spike on the N/side.

Measured		N78°E	19.80'
----------	--	-------	--------

White Pine	5	N38°W	35½ lks. (23.43')
------------	---	-------	-------------------

Found standing dead.

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION