

**SURVEY & REMONUMENTATION**

MAY 05 1997

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

**COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 33W	H-7
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in*Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 742-743.

*Fields McAntyre*  
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-7; One-quarter Corner common to Sections 15 and 22, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7; One-quarter Corner common to Sections 15 and 22, T51N, R33W;

Found a 2 1/2" diameter aluminum pipe with a 3" aluminum cap projecting 12 inches above the ground as set by the BLM in 1984. The position of this monument was verified by a traverse. I did not remonument the corner but stamped "PA 345 1996" to the cap. Accepted as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7; One-quarter Corner common to Sections 15 and 22, T51N, R33W;

Found a 2 1/2" aluminum pipe with a 3" aluminum cap stamped as to location projecting 12 inches above the ground.

i) Set 7" spike	SE/side	9" White Pine	N42°E	11.94'
ii) Set 7" spike	N/side	6" Red Maple	S48°E	24.75'
iii) Set 7" spike	SW/side	8" Red Oak	S26°E	54.17'
iv) Set 7" spike	W/side	11" Red Oak	N23°W	62.70'
v)		Location Post	North	3.0'

(i), (iii), and (iv) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red. (ii) is a BLM new bearing tree and is further described in Part A.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4		3		2		1			
3												
4	7	8	9		10		11		12			
5												
6	18	17	16		15		14		13			
7												
8	19	20	21		22		23		24			
9												
10	30	29	28		27		26		25			
11												
12	31	32	33		34		35		36			
13												

APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Baraga County

*Michael Mileski*  
 12-18-96



Signed by *Michael Mileski*  
 Surveyor's Michigan License No. 39091

Date 18 Dec 1996

A. Description of original monument and accessories and/or subsequent restoration:

H-7; One-quarter Corner common to Sections 15 and 22, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a maple post witnessed by a

White Pine	30	N73°W	43 lks.
White Pine	20	N47°E	23 lks.

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, this corner was reestablished at record U.S. bearing and distance from the section corner to the west. The BLM monumented this position with a 2½" x 30" aluminum pipe and cap witnessed by a

Maple	5	S46°E	37½ lks. (24.75')
-------	---	-------	-------------------

Presently alive and 6" in diameter having a partially healed lower blaze with scribing visible. I added an upper blaze and painted both blazes red as well as a band around the tree at the upper blaze. Set a 7" spike on the N/side.

Measured		S48°E	24.75'
----------	--	-------	--------

White Pine	6	N29°W	30 lks. (19.80')
------------	---	-------	------------------

Found stump.

Measured		N31°W	19.8'
----------	--	-------	-------

SURVEY &  
REMONUMENTATION

MAY 05 1997

COMMISSION