

**SURVEY &
REMONUMENTATION**

MAY 05 1997

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>L-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 3RD
DAY OF JANUARY, 1997 AT 10:30
A.M. AND RECORDED IN LIBER 4
OF LAND CORNER RECORDATION
RECORDS ON PAGES 744-745.

Richard McAntyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-11; One-quarter Corner common to Sections 25 and 36, T51N, R33W;
See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11; One-quarter Corner common to Sections 25 and 36, T51N, R33W;

Found a 3/4" x 24" solid iron rod three inches below the road surface. This monument was found to be badly bent to the north near the surface but straightened out to its original position further down. This monument fit well with the remaining two 1979 Crampton accessories as described in Part A. The monument is located in the center of Indian Cemetery Road a distance of 16 feet east of the centerline of Skanee Road. Replaced the found iron rod with a 1" (I.D.) x 36" galvanized iron pipe and cap. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11; One-quarter Corner common to Sections 25 and 36, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location 6 inches below the road surface in a monument box.

i)	Set 7" spike	SE/side	Utility Pole	N58°E	61.66'
ii)	Set 7" spike	SE/side	Utility Pole	N66°E	78.96'
iii)	Set 7" spike	E/side	Utility Pole	S40°E	29.83'
iv)	Set 7" spike	N/side	Utility Pole	S72°W	65.35'
v)	Set 7" spike	E/side	8" Spruce	N30°W	82.08'

(i) and (iii) are 1979 Crampton accessories and are further described in Part A.

(iv) and (v) are 1995 Crampton accessories and are further described in Part A.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-18-96
[Signature]



Signed by *Michael Mileski*

Date 19 Dec 1996

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

L-11; One-quarter Corner common to Sections 25 and 36, T51N, R33W;

Originally established during U.S. Survey conducted by Harvey Mellen, D.S. in 1845 and monumented with a hemlock post witnessed by a

Sugar 12 N83°E 28 lks.

Yellow Birch 36 S31°W 69 lks.

On 30 May 1979, Robert Crampton, PS #24591 recovered and accepted a "3/4" iron bar in Indian Cemetery Road and 3 foot off pavement on southerly side of M-35". According to a Land Corner Recordation Certificate prepared by Mr. Crampton and recorded on 30 August 1979 in Liber 1 on page 356 of the Baraga County Land Corner Records, this monument is of unknown origin. Mr. Crampton left the monument in place and noted the following accessories:

Survey Tag in Utility Pole N55°E 61.62'
Set a 7" spike directly below a small nail and tag marked "LLS 24591" on the SE/side.
Measured N58°E 61.66'

Survey Tag in Utility Pole S50°E 29.80'
Set a 7" spike directly below a small nail and tag marked "LLS 24591" on the E/side.
Measured S40°E 29.83'

Survey Tag in Utility Pole S80°W 60.43'
Gone.

On 10 August 1994, Mr. Crampton recovered a p-k nail which was in agreement with his 1979 accessories. Mr. Crampton recorded another Land Corner Recordation Certificate on 16 February 1995. See LCRC, Liber 4 on page 546. The 1995 LCRC indicates two additional accessories as follows:

Survey Tag in Utility Pole S85°W 65.28'
Set a 7" spike directly below a small nail and tag marked "LLS 24591" on the N/side.
Measured S72°W 65.35'

8" Spruce N28°W 81.49'
Presently alive and 11" in diameter.
Set a 7" spike directly below a small nail and tag marked "LLS 24591".
Measured N30°W 82.08'

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, an "iron bar, 3/4 in. diam., firmly set, 6 ins. below the surface" as recorded by Mr. Crampton was found and accepted. The BLM did not remonument the corner. Their ties to Mr. Crampton's 1979 accessories are as follows:

Power Pole N55°E 93½ lks. (61.71')
Power Pole S50°E 45 lks. (29.70')
Power Pole S80°W 91½ lks. (60.39')

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION