

SURVEY & REMONUMENTATION

MAY 05 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>33W</u>	<u>M-10*</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 3RD DAY OF JANUARY, 1997 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGES 752-753.

Helda Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on December, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-10; East One-quarter Corner Section 25, T51N, R33W;

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10; East One-quarter Corner Section 25, T51N, R33W;

Found a 3/4" x 27" iron rod 6 inches below the surface of an old dirt road. On the north side of this iron rod a 3/4" x 18" iron rod and cap marked "LS 32432" (Jerry Taylor) was found. Replaced the found iron rod with a 1"(I.D.) x 36" galvanized iron pipe and cap. Corner is located 32 feet north of the physical centerline of Taylor Road. Accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10; East One-quarter Corner Section 25, T51N, R33W;

Set a 1" (I.D.) x 36" galvanized iron pipe with a 2" aluminum cap stamped as to location 6 inches below ground.

i)	Set 7" spike	W/side	10" Red Oak	N08°E	40.97'
ii)	Set 7" spike	W/side	10" White Birch	N30°E	34.22'
iii)	Set 7" spike	SE/side	12" Red Oak	N62°E	15.22'
iv)	Set 7" spike	SE/side	8" Red Oak	S37°W	82.25'
v)	Set 7" spike	SW/side	5" Hemlock	N62°W	20.30'
vi)			Location Post	West	10.0'

(i), (iii), (iv), and (v) are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze were painted red.

(ii) is a 1979 Crampton new bearing tree and is further described in Part A.

* This corner is also A-10 of T51N, R32W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-18-96



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 19 Dec 1996

LIBER 4 PAGE 752

A. Description of original monument and accessories and/or subsequent restoration:

M-10; East One-quarter Corner Section 25, T51N, R33W;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Hemlock 24 S89°W 29 lks.

Hemlock 14 N42°W 27 lks.

On 30 May 1979, Robert Crampton, PS #24591 recovered and accepted a "3/4" iron bar found 16' North of "T" Road on an Old 2 rut road". According to a Land Corner Recordation Certificate prepared by Mr. Crampton and recorded on 30 August 1979 in Liber 1 on page 346 of the Baraga County Land Corner Records, this monument is of unknown origin. Mr. Crampton left the monument in place and noted the following new bearing trees:

9" Maple S80°W 28.55'
Gone.

9" Birch East 16.49'
Gone.

9" Birch N30°E 34.11'

Found a white birch presently alive and 10" in diameter.

Set a 7" spike directly below an overgrown nail and tag on the Wside. No blazes or markings were added to this tree.

Measured N30°E 34.22'

During the course of a survey conducted by Stephen Douglas of the Bureau of Land Management from 10 May 1984 to 10 November 1984 and approved 23 September 1985, a 3/4" diameter iron rod as recorded by Mr. Crampton in 1979 was found and accepted. The BLM indicates a tie to one of Mr. Crampton's new bearing trees as follows:

White Birch 9 N28°E 52½ lks. (34.65')

The BLM did not remonument the corner but did note the following new bearing tree:

White Birch 12 N20°W 117 lks. (77.22')

Found standing dead.

Measured N20°W 76.4'

SURVEY &
REMONUMENTATION

MAY 05 1997

COMMISSION