

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>51</u> N. <u>X</u> , R. <u>34</u> K. <u>W.</u>	<u>E11</u>
2. PROPERTY CONTROLLING IN SECTION <u>33</u>	T. <u>51</u> N. <u>X</u> , R. <u>34</u> K. <u>W.</u>	<u>16, 2</u>
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____, R. _____ E. <u>W.</u>	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 18, 1978, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on October 18, 1978, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
 Corner E11: Original Monument and Accessories Not Found. Found old Cedar posts at fence intersection, witnessed by G. G. Neault in 1953.  
 Corner 16: Not Set on Original Survey Nor Subsequently Apparently.  
 Corner 2: Not Set on Original Survey Nor Subsequently Apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
 Corner E11: Restored at old post.  
 Corner 16: Established by proportion between corners east and west.  
 Corner 2: Established by proportion between corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Corner E11: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
 7" Cedar N15W 21.8 ft. S29,NBT  
 4" Cedar N69E 19.2 ft. S28,NBT  
 9" Cedar S61W 9.6 ft. S32,NBT  
 Corner 2: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
 9" Cedar S13E 20.2 ft. 1/16S,BT  
 6" Cedar N16E 47.4 ft. 1/16S,BT  
 9" Sugar N83W 31.2 ft. 1/16S,BT  
 Corner 16: Set 1" I.D. x 36" Iron Pipe with 4" aluminum cap.  
 8" Cedar S53W 61.8 ft. 1/16S,BT  
 8" Cedar S52E 40.5 ft. 1/16S,BT  
 6" Cedar N59E 35.7 ft. 1/16S,BT

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE October 24, 1978

CHIEF OF SURVEY PARTY  
 MICHIGAN REGISTERED LAND SURVEYOR  
 Keith L. Sackett  
 Department of Natural Resources



SURVEYOR'S MICHIGAN REGISTRATION NO. 19006