

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

BARAGA COUNTY

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 51 <sup>N.</sup> <del>36</del> R. 34 <sup>W.</sup> <del>35</del>	A5, B5, C5
2. PROPERTY CONTROLLING IN SECTION	T. _____ S. R. _____ E. W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ S. R. _____ E. W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 22, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner A5: Original monument and accessories not found. Found 3/4" iron pipe buried in N-S-E-W county road intersection.
  - Corner B5: Original monument and accessories not found. Found 3/8" iron pin buried in intersection N-S-E-W roads.
  - Corner C5: Original monument and accessories not found. Found 3/8" iron pin buried in east west road in line with old fences north and south.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner A5: Restored at 3/4" iron pipe.
  - Corner B5: Restored at 3/8" iron pin.
  - Corner C5: Restored at 3/8" iron pin.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner A5: 3/4" iron pipe buried in N-S-E-W county road intersection.  
DNR tag and nail: 7" Balsam S43W 49.79 ft.  
9" Maple N74E 70.89 ft.  
Underground cable marker post S43E 62.9 ft.
  - Corner B5: 3/8" iron pin buried in intersection N-S-E-W roads  
Telephone junction box N46E 69.3 ft.  
DNR tag and nail in: 10" Maple S33E 79.80 ft.  
P. Pole S42W 51.28 ft.
  - Corner C5: 3/8" iron pin. DNR tag and nail in: P. Pole S65E 70.15 ft.  
5" Maple N51W 73.68 ft.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Keith L. Sackett DATE 1-26-82  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR  
**Keith L. Sackett**  
 Michigan Dept. of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006