

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	BARAGA COUNTY LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>51</u> N. <u>X</u> , R. <u>34</u> W. <u>X</u>	B3
2. PROPERTY CONTROLLING IN SECTION _____	T. <u>51</u> N. <u>X</u> , R. <u>34</u> W. <u>X</u>	2, 5, 6
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____, R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Keith L. Sackett, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on See Below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- Corner B3: Original monument and accessories not found.
- Corner 2: Not set on original survey.
- Corner 5: Not set on original survey nor subsequently apparently.
- Corner 6: Not set on original survey nor subsequently apparently.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- Corner B3: Restored 8-18-81 by proportion between corner locations east and west.
- Corner 2: Established 8-19-81 on line between corners east and west.
- Corner 5: Established 8-26-81 during section subdivision.
- Corner 6: Established 8-26-81 during section subdivision.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <ul style="list-style-type: none"> Corner B3: Set 1" I.D.x32" iron pipe with 4" alum. cap. 5" Sugar S05W 23.8 ft. 1/4S,NBT 3" Maple N55W 11.2 ft. 1/4S,NBT 6" squared spruce S50E 2.5 ft. marked 1/4,7,6 Corner 2: Set 1" I.D.x32" iron pipe with 4" alum. cap. 18" Cedar S68W 35.5 ft. 1/16S,BT 8" Cedar S07E 44.8 ft. 1/16S,BT 12" Cedar N38E 31.9 ft. 1/16S,BT Corner 5: Set 1" I.D.x32" iron pipe with 4" alum. cap. 6" Maple N59E 11.1 ft. 1/16S,BT 5" Sugar S20W 26.4 ft. 1/16S,BT 6" Maple N55W 24.7 ft. 1/16S,BT | <ul style="list-style-type: none"> Corner 6: Set 1" I.D.x32" Iron Pipe with 4" alum. cap. 6" Maple N62W 8.0 ft. 1/16S,BT 7" Sugar S64W 12.9 ft. 1/16S,BT 9" Sugar N75E 4.8 ft. 1/16S,BT |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Keith L. Sackett DATE 10-22-81

CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR
 Keith L. Sackett
 Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 19006